

UNION COUNTY PUBLIC WORKS



853W ZONE IMPROVEMENTS PHASE I TRANSMISSION MAINS ROCKY RIVER ROAD & SECREST SHORT CUT ROAD

UNION COUNTY PUBLIC WORKS PROJECT NUMBER WT-061
B&V PROJECT NO. 186110


JANUARY 2021

BID SET



Black & Veatch International Company

Business License No. F-0794
10925 David Taylor Drive, Suite 280
Charlotte, North Carolina 28262



VICINITY MAP
NO SCALE


NOTES:

- REFER TO NOTE 2 ON SHEET A1 FOR UTILITY CONFLICTS INCLUDING BUT NOT LIMITED TO UTILITY POLES, WIRES, AND ANCHORS.
- CONTRACTOR SHALL PROTECT EXISTING FIRE HYDRANT AND ANY DAMAGE TO THE HYDRANT SHALL BE REPAIRED OR REPLACED AT THE CONTRACTORS EXPENSE.
- CONTRACTOR SHALL REMOVE AND REPLACE 30 LINEAR FEET OF EXISTING 8" PVC WITH PROTECTO 401 LINED CLASS 350 DIP AT A CONSTANT SLOPE. CONNECT NEW SEWER TO EXISTING SEWER HYMAX COUPLING OR APPROVED EQUAL.
- CONTRACTOR WILL REPLANT TREES OF LIKE-KIND THAT MAY BE REMOVED AS PART OF THE WORK. TREES WILL BE "STARTER TREES" IN SIZE RANGING IN HEIGHT OF 6FT-8FT. CALIPER MEASUREMENT OF TREE AT BASE SHALL NOT EXCEED 3-INCH DIAMETER. CONTRACTOR SHALL COORDINATE WITH OWNER/ENGINEER AS TO DESIRED LOCATION OF SAID TREES ON PARCEL.


- CONTRACTOR SHALL PROTECT TELEPHONE PEDESTAL AND ANY DAMAGE SHALL BE REPAIRED/REPLACED AT THE CONTRACTORS EXPENSE IMMEDIATELY.
- REMOVE AND REPLACE 25 FT STRIP OF PARKING AREA ADJACENT TO CONSTRUCTION AND RE-STRIP TO MATCH EXISTING.
- CONTRACTOR SHALL REMOVE AND REPLACE TEMPORARY SEDIMENT FENCE PARALLEL TO CREEK OR DRAINAGE SWALE TO PREVENT SEDIMENT RUNOFF INTO THE CREEK OR DRAINAGE SWALE WHEN CONSTRUCTING THE WATERLINE.
- EXISTING WATERLINE SHOWN IS BASED OFF GIS AND IS APPROXIMATE. CONTRACTOR SHALL FIELD LOCATE UTILITY AND COORDINATE WITH OWNER/ENGINEER PRIOR TO PERFORMING ANY WORK.
- EXISTING GAS LINE IS SHOWN BASED ON SITE VISIT INFORMATION AND IS APPROXIMATE. CONTRACTOR SHALL CONFIRM LOCATION, DEPTH, AND SIZE PRIOR TO PERFORMING ANY WORK IN THE AREA.
- CONTRACTOR TO POLYWRAP TRANSMISSION MAIN PER SPECIFICATIONS WITHIN STA 66+00 TO STA 67+60 WHERE EXISTING GAS LINE TO THE EAST IS WITHIN 10' HORIZONTAL SEPARATION.
- CONTRACTOR TO POLYWRAP TRANSMISSION MAIN PER SPECIFICATIONS WITHIN STA 70+36.85 TO STA 71+00 WHERE EXISTING GAS LINE TO THE EAST IS WITHIN 10' HORIZONTAL SEPARATION.
- PROVIDE EROSION CONTROL MATTING FOR THE FULL WIDTH OF DISTURBED AREA FROM STA 70+36 TO STA 71+00.
- PROPOSED WATERMAIN SHALL BE POLYWRAPPED AS SPECIFIED A MINIMUM OF 100 LF CENTERED OVER GAS CROSSING. PROPOSED WATERMAIN SHALL ADDITIONALLY BE INSTALLED WITHIN A 54" SN46 FIBERGLASS REINFORCED CASING PIPE AS SHOWN ON DRAWINGS. FRP PIPE ENCASEMENT SHALL BE INSTALLED WITH SPIDERS AND END SEALS AS SPECIFIED.

MATCHLINE - STA 60+00
FOR CONTINUATION SEE SHEET C5


MATCHLINE - STA 71+00
FOR CONTINUATION SEE SHEET C7



PLAN
1" = 40'



PROFILE
4' 0' 4' 8'




Black & Veatch International Company
Business License No. F-0794
10925 David Taylor Drive, Suite 280
Charlotte, North Carolina 28262

**UNION COUNTY PUBLIC WORKS
853W ZONE IMPROVEMENTS
PHASE I TRANSMISSION MAINS**

CIVIL
PLAN AND PROFILE
STA 60+00 TO STA 71+00

DESIGNED: MLT, WPS
DETAILED: KTH
CHECKED: CES
APPROVED: SLT
DATE: JANUARY 2021



PROJECT NO.
186110
C6
SHEET
10 OF 42


BID SET

FD700_PW
D10000

NO.	BY	CHK/APP

DATE


REVISIONS AND RECORD OF USE



MATCHLINE - STA 80+00
FOR CONTINUATION SEE SHEET C8

NOTES:

1. REFER TO NOTE 2 ON SHEET A1 FOR UTILITY CONFLICTS INCLUDING BUT NOT LIMITED TO UTILITY POLES, WIRES, AND ANCHORS.
2. CONTRACTOR SHALL PROTECT EXISTING FIRE HYDRANT AND ANY DAMAGE TO THE HYDRANT SHALL BE REPAIRED OR REPLACED AT THE CONTRACTORS EXPENSE.
3. CONTRACTOR SHALL PROTECT EXISTING WATER SERVICE, VAULT, AND HYDRANT AND MAINTAIN WATER SERVICE. ANY INTERRUPTION TO WATER SERVICE SHALL BE COORDINATED AND APPROVED WITH THE OWNER/ENGINEER AND BUSINESS OWNER PRIOR TO PERFORMING ANY WORK.
4. CONTRACTOR WILL REPLANT TREES OF LIKE-KIND THAT MAY BE REMOVED AS PART OF THE WORK. TREES WILL BE "STARTER TREES" IN SIZE RANGING IN HEIGHT OF 6FT-8FT. CALIPER MEASUREMENT OF TREE AT BASE SHALL NOT EXCEED 3-INCH DIAMETER. CONTRACTOR SHALL COORDINATE WITH OWNER/ENGINEER AS TO DESIRED LOCATION OF SAID TREES ON PARCEL.
5. APPROXIMATE LOCATION OF EXISTING AC WATERLINE IS SHOWN IN PLAN. CONTRACTOR SHALL FIELD VERIFY LOCATION PRIOR TO PERFORMING ANY WORK. CONTRACTOR SHALL TAKE NECESSARY MEASURES TO PROTECT AND TEMPORARILY SUPPORT EXISTING WATERLINE DURING CONSTRUCTION.
6. CONTRACTOR SHALL PROTECT EXISTING SIGN, AND PLANTING AREA; AND IF CONSTRUCTION ACTIVITIES REQUIRE REMOVAL AND STOCKPILE, CONTRACTOR SHALL COORDINATE REPLACEMENT LOCATION WITH THE OWNER/ENGINEER. REMOVAL, STOCKPILE, AND REPLACEMENT IF REQUIRED IS AT THE CONTRACTORS EXPENSE.
7. CONSTRUCTION EQUIPMENT / TRAFFIC ARE AT NO TIME ALLOWED TO USE ASPHALT DRIVEWAY EXCEPT FOR CONSTRUCTION OF TEMPORARY PARKING AREA. ASPHALT PARKING LOT AND SOUTH DRIVEWAY ARE TO BE REPAIRED AND PAVED WITHIN ONE WEEK OF COMPLETION OF PIPE INSTALLATION ACROSS ASPHALT AREAS ON THE PROPERTY. PROVIDE TEMPORARY STRIPING IMMEDIATELY TO MATCH EXISTING. PROVIDE PERMANENT STRIPING ONCE PAVEMENT HAS CURED.
8. EXISTING WATERLINE SHOWN IS APPROXIMATE AND CONTRACTOR SHALL FIELD LOCATE THE WATERLINE AND COORDINATE WITH OWNER/ENGINEER PRIOR TO PERFORMING ANY WORK.
9. INSTALL TEMPORARY GRAVEL PARKING AREA. UPON COMPLETION OF CONSTRUCTION ALONG PARCEL 20 REMOVE TEMPORARY GRAVEL PARKING AREA AND RESEED DISTURBED AREA.
10. APPROXIMATE LOCATION OF EXISTING ABOVE GRADE UTILITY BOX. CONTRACTOR SHALL FIELD LOCATE UTILITY BOX AND REMOVE AND REPLACE TO PERFORM PROPOSED WORK. ALL COSTS ASSOCIATED WITH REMOVAL AND REPLACEMENT OF UTILITY BOX WILL BE AT THE CONTRACTORS EXPENSE.
11. CONTRACTOR TO POLYWRAP TRANSMISSION MAIN PER SPECIFICATIONS WITHIN STA 74+00 TO STA 72+50 WHERE EXISTING GAS LINE TO THE EAST IS WITHIN 10' HORIZONTAL SEPARATION.
12. PROVIDE EROSION CONTROL MATTING FOR THE FULL WIDTH OF DISTURBED AREA FROM STA 71+00 TO STA 72+50.



PROFILE




MATCHLINE - STA 71+00
FOR CONTINUATION SEE SHEET C6

	<p>BLACK & VEATCH</p> <p>Black & Veatch International Company 10925 David Taylor Drive, Suite 280 Charlotte, North Carolina 28262</p>
<p>UNION COUNTY PUBLIC WORKS 853W ZONE IMPROVEMENTS PHASE I TRANSMISSION MAINS</p>	
<p>CIVIL PLAN AND PROFILE STA 71+00 TO STA 80+00</p>	
<p>DESIGNED: MLT, WPS DETAILED: KTH CHECKED: CES APPROVED: SLT DATE: JANUARY 2021</p>	
<p>IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE</p>	
<p>PROJECT NO. 186110</p>	
<p>C7 SHEET 11 OF 42</p>	

BID SET


FD7005_PW
D10000



- NOTES:**
- REFER TO THE CSX PIPELINE DESIGN & CONSTRUCTION SPECIFICATIONS FOR ADDITIONAL INFORMATION.
 - THE FRONT OF THE PIPE SHALL BE PROVIDED WITH MECHANICAL ARRANGEMENTS OR DEVICES THAT WILL POSITIVELY PREVENT THE AUGER FROM LEADING THE PIPE SO THAT NO UNSUPPORTED EXCAVATION IS AHEAD OF THE PIPE.
 - THE OPERATION SHALL BE PROCEEDED ON A 24-HOUR BASIS WITHOUT STOPPAGE (EXCEPT FOR ADDING LENGTHS OF PIPE) UNTIL THE LEADING EDGE OF THE PIPE HAS REACHED THE RECEIVING PIT. THE AUGER AND CUTTING HEAD ARRANGEMENT SHALL BE REMOVABLE FROM WITHIN THE PIPE IN THE EVENT AN OBSTRUCTION IS ENCOUNTERED.
 - PIPELINE SHALL BE PROMINENTLY MARKED AT BOTH SIDES OF THE CSX PROPERTY LINES BY DURABLE, WEATHERPROOF SIGNS LOCATED OVER THE CENTERLINE OF THE PIPE IN ACCORDANCE WITH CSX SPECIFICATIONS.
 - NO CONSTRUCTION OR ENTRY UPON THE CSX CORRIDOR IS PERMITTED UNTIL THE DOCUMENT TRANSACTION IS COMPLETED, YOU ARE IN RECEIPT OF A FULLY EXECUTED DOCUMENT, AND YOU HAVE OBTAINED AUTHORITY FROM THE LOCAL ROADMASTER.
 - IF REQUIRED, A DEWATERING PLAN IN ACCORDANCE WITH CSX SPECIFICATIONS WILL BE SUBMITTED TO THE CSX REPRESENTATIVE FOR REVIEW AND APPROVAL PRIOR TO ANY DEWATERING OPERATIONS.
 - BLASTING IS NOT PERMITTED UNDER OR ON CSX PROPERTY. SEE CSX873182 EXHIBIT A.
 - CSX DOES NOT GRANT OR CONVEY AN EASEMENT FOR THIS INSTALLATION.
 - EXISTING PIPES TO BE ABANDONED WILL BE COMPLETELY FILLED WITH CEMENT GROUT, COMPACTED SAND, OR FLOWABLE FILL.
 - REFER TO PROJECT SPECIFICATIONS FOR CSX RAILROAD ENCROACHMENT AGREEMENT.
 - STEEL CASING PIPE SHALL BE SPIRAL WELDED STEEL WITH A MINIMUM WALL THICKNESS EQUAL TO 0.781 INCHES AND A MINIMUM YIELD STRENGTH EQUAL TO 35,000 PSI.
 - CONTRACTOR SHALL PROVIDE DURABLE WEATHERPROOF SIGNS ON BOTH SIDES OF TRACK AT RR RW LINES LOCATED OVER THE CENTERLINE OF THE PIPE PER CSX TRANSPORTATION DESIGN AND CONSTRUCTION STANDARD SPECIFICATIONS.
 - CONTRACTOR SHALL FOLLOW THE LATEST EDITION OF THE CSX TRANSPORTATION DESIGN & CONSTRUCTION STANDARD SPECIFICATIONS.
 - CONTRACTOR SHALL PROVIDE GEOTECHNICAL MONITORING POINTS PER SPECIFICATION 02309. LOCATION OF SURFACE MONITORING POINT IS APPROX. CONTRACTOR SHALL ADJUST AS NEEDED.
 - REFER TO NOTE 2 ON SHEET A1 FOR UTILITY CONFLICTS INCLUDING BUT NOT LIMITED TO UTILITY POLES, WIRES AND ANCHORS.
 - EXISTING 8" WATERLINE SHOWN IS BASED OFF GIS AND IS APPROXIMATE. CONTRACTOR SHALL FIELD LOCATE UTILITY AND COORDINATE WITH OWNER/ENGINEER PRIOR TO PERFORMING ANY WORK.

PIPELINE CONTENT DETAILS	
COMMODITY DESCRIPTION	POTABLE WATER TRANSMISSION MAIN
MAXIMUM OPERATING PRESSURE:	150 PSI
IS COMMODITY FLAMMABLE:	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
PIPE MATERIAL:	CARRIER PIPE: DUCTILE IRON CASING PIPE: STEEL
MATERIAL SPECIFICATIONS & GRADE:	ANSI/AWWA C151 / N/A
SPECIFIED MINIMUM YIELD STRENGTH:	42,000 PSI / 35,000 PSI
NOMINAL SIZE OUTSIDE DIAMETER (INCHES):	38.3000 / 55.5600
WALL THICKNESS (INCHES):	0.4700 / 0.7810
TYPE OF SEAM:	N/A / SPIRAL WELDED
TYPE OF JOINTS:	RESTRAINED DUCTILE IRON / WELDED
TUNNEL LINER PLATES REQUIRED:	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
CATHODIC PROTECTION:	<input checked="" type="checkbox"/> YES <input type="checkbox"/> NO TYPE: POLYETHYLENE WRAP
PROTECTIVE COATING:	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO TYPE:
TEMP. TRACK SUPPORT OR RIP-RAP REQ.:	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO MUST DESCRIBE & SHOW ON DWG.

PLAN
1" = 40'



PROFILE
HORIZONTAL SCALE 1"=40'
VERTICAL SCALE 1"=4'

DESIGNED: MLT, WPS
 DETAILED: KTH
 CHECKED: CES
 APPROVED: SLT
 DATE: JANUARY 2021

0 1/2 1
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE

PROJECT NO. 186110
C12
 SHEET 16 OF 42

BLACK & VEATCH
 Black & Veatch International Company
 Business License No. F-0794
 10925 David Taylor Drive, Suite 280
 Charlotte, North Carolina 28262


UNION COUNTY PUBLIC WORKS
 853W ZONE IMPROVEMENTS
 PHASE I TRANSMISSION MAINS

CIVIL
 PLAN AND PROFILE
 STA 120+00 TO STA 131+00


NOTES: (continued from previous page)

FD7005_PW
 D10000

BID SET



PLAN
1" = 40'



PROFILE



- NOTES:**
- REFER TO NOTE 2 ON SHEET A1 FOR UTILITY CONFLICTS INCLUDING BUT NOT LIMITED TO UTILITY POLES, WIRES, AND ANCHORS.
 - CONTRACTOR SHALL GRADE (CUT) EXISTING SOIL MOUND TO AN ELEVATION OF 655 AND GRADE TO PROVIDE POSITIVE DRAINAGE. SLOPE SHALL NOT EXCEED 2H:1V. CONTRACTOR SHALL DISPOSE OF EXISTING SOILS. ALL CONSTRUCTION ACTIVITIES INCLUDING GRADING SHALL BE PERFORMED WITHIN THE EASEMENTS OR A RIGHT OF ENTRY MUST BE OBTAINED FROM THE PROPERTY OWNER.
 - EXISTING 8" WATERLINE SHOWN IS BASED OFF GIS AND IS APPROXIMATE. CONTRACTOR SHALL FIELD LOCATE UTILITY AND COORDINATE WITH OWNER/ENGINEER PRIOR TO PERFORMING ANY WORK.
 - EASEMENT INFORMATION SHOWN IN PLAN IS THE RECORDED EASEMENT INFORMATION. THE NORTH CAROLINA NATURAL GAS CORPORATION IS NOW OWNED BY DUKE ENERGY/PIEDMONT NATURAL GAS.
 - PROPOSED WATERMAIN SHALL BE POLYWRAPPED AS SPECIFIED A MINIMUM OF 100 LF CENTERED OVER GAS CROSSING. PROPOSED WATERMAIN SHALL ADDITIONALLY BE INSTALLED WITHIN A 54" SN46 FIBERGLASS REINFORCED CASING PIPE AS SHOWN ON DRAWINGS. FRP PIPE ENCASEMENT SHALL BE INSTALLED WITH SPIDERS AND END SEALS AS SPECIFIED.


	NO. BY: CHK/APP REVISIONS AND RECORD OF USE DATE
Black & Veatch International Company Business License No. F-0794 10925 David Taylor Drive, Suite 280 Charlotte, North Carolina 28262	
UNION COUNTY PUBLIC WORKS 853W ZONE IMPROVEMENTS PHASE I TRANSMISSION MAINS	
CIVIL PLAN AND PROFILE STA 177+00 TO STA 188+50	
DESIGNED: MLT, WPS DETAILED: KTH CHECKED: CES APPROVED: SLT DATE: JANUARY 2021	
<p>IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE</p>	
PROJECT NO. 186110 C18 SHEET 22 OF 42	

BID SET


FD7005_PW
D10000

MATCHLINE - STA 199+00
FOR CONTINUATION SEE SHEET C19

MATCHLINE - STA 210+00
FOR CONTINUATION SEE SHEET C20




- NOTES:**
- REFER TO NOTE 2 ON SHEET A1 FOR UTILITY CONFLICTS INCLUDING BUT NOT LIMITED TO UTILITY POLES, WIRES, AND ANCHORS.
 - CONTRACTOR SHALL PROTECT EXISTING FIRE HYDRANT AND ANY DAMAGE TO THE HYDRANT SHALL BE REPAIRED OR REPLACED AT THE CONTRACTOR'S EXPENSE.
 - CONTRACTOR SHALL REMOVE AND REPLACE 30 LINEAR FEET OF EXISTING 8" PVC WITH A 30 FT STICK OF PROTECTO 401 LINED CLASS 350 DIP. CONNECT NEW SEWER TO EXISTING SEWER WITH A HYMAX COUPLING OR APPROVED EQUAL.
 - CONTRACTOR WILL REPLANT TREES OF LIKE-KIND THAT MAY BE REMOVED AS PART OF THE WORK. TREES WILL BE "STARTER TREES" IN SIZE RANGING IN HEIGHT OF 6FT-8FT. CALIPER MEASUREMENT OF TREE AT BASE SHALL NOT EXCEED 3-INCH DIAMETER. CONTRACTOR SHALL COORDINATE WITH PROPERTY OWNER AS TO DESIRED LOCATION OF SAID TREES ON PARCEL.
 - CONTRACTOR TO COORDINATE LOCATION OF EXISTING GAS LINE WITH STONE OUTLET LOCATION, 3 LOCATIONS.



NO.	BY	CHK/APP

REVISIONS AND RECORD OF USE



BLACK & VEATCH
Black & Veatch International Company
Business License No. F-0794
10925 David Taylor Drive, Suite 280
Charlotte, North Carolina 28262

UNION COUNTY PUBLIC WORKS
853W ZONE IMPROVEMENTS
PHASE I TRANSMISSION MAINS



CIVIL
PLAN AND PROFILE
STA 199+00 TO STA 210+00

DESIGNED: MLT, WPS
DETAILED: KTH
CHECKED: CES
APPROVED: SLT
DATE: JANUARY 2021


PROJECT NO.
186110
C20
SHEET
24 OF 42

BID SET

FD700_PW
D10000



PLAN
1" = 40'




PROFILE



NOTES:

- REFER TO NOTE 2 ON SHEET A1 FOR UTILITY CONFLICTS INCLUDING BUT NOT LIMITED TO UTILITY POLES, WIRES, AND ANCHORS.
- CONTRACTOR SHALL PROTECT EXISTING FIRE HYDRANT AND ANY DAMAGE TO THE HYDRANT SHALL BE REPAIRED OR REPLACED AT THE CONTRACTORS EXPENSE.
- CONTRACTOR WILL REPLANT TREES OF LIKE-KIND THAT MAY BE REMOVED AS PART OF THE WORK. TREES WILL BE "STARTER TREES" IN SIZE RANGING IN HEIGHT OF 6FT-8FT. CALIPER MEASUREMENT OF TREE AT BASE SHALL NOT EXCEED 3-INCH DIAMETER. CONTRACTOR SHALL COORDINATE WITH OWNER/ENGINEER AS TO DESIRED LOCATION OF SAID TREES ON PARCEL.
- CONTRACTOR SHALL CLEAR THE REMAINING WOODED AREA EAST OF EASTERN EDGE OF THE PERMANENT EASEMENT ON PARCEL NO. 75 (APPROXIMATELY 25 FEET) BETWEEN THE PROPOSED EASEMENT AND THE HOUSE. THE CONTRACTOR WILL REMOVE ALL VEGETATION AND ONLY CUT TREES DOWN TO THE STUMP AND WILL NOT GRADE THE ADDITIONAL AREA OUTSIDE OF THE EASEMENT. CONTRACTOR SHALL COORDINATE WITH PROPERTY OWNER PRIOR TO PERFORMING ANY CLEARING.
- CONTRACTOR SHALL REMOVE A PORTION OF THE WOODEN FENCE LOCATED WITHIN THE PROPOSED EASEMENT. UPON COMPLETION OF ALL WORK ON THIS PROPERTY THE FENCE SHALL BE PUT BACK IN ORIGINAL OR BETTER CONDITION AND LOCATION.
- CONTRACTOR WILL REPLANT TREES OF LIKE-KIND THAT MAY BE REMOVED AS PART OF THE WORK. TREES WILL BE "STARTER TREES" IN SIZE RANGING IN HEIGHT OF 6FT-8FT. CALIPER MEASUREMENT OF TREE AT BASE SHALL NOT EXCEED 3-INCH DIAMETER. SPACING OF TREES SHALL BE SIX (6) FEET ON CENTER TWO ROWS STAGGERED PLACEMENT. CONTRACTOR SHALL COORDINATE WITH OWNER/ENGINEER AS TO DESIRED LOCATION OF SAID TREES ON PARCEL.
- CONTRACTOR WILL RELOCATE SHED AND DOG HOUSE TO JUST OUTSIDE PERMANENT EASEMENT AND CONNECT RELOCATED FENCE.
- CONTRACTOR WILL REMOVE ANY PORTION OF THE WOODEN FENCE LOCATED WITHIN THE PROPOSED EASEMENTS AND UPON COMPLETION OF THE PROJECT, CONTRACTOR WILL REINSTALL THE FENCE BACK TO ITS ORIGINAL LOCATION AND EXTEND ADDITIONAL FENCING TO RELOCATED SHED TO PROVIDE COMPLETE ENCLOSURE OF FENCING FOR DOG. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING TEMPORARY CONTAINMENT FENCING FOR DOG DURING CONSTRUCTION.
- EXISTING 8" WATERLINE SHOWN IS BASED OFF GIS AND IS APPROXIMATE. CONTRACTOR SHALL FIELD LOCATE UTILITY AND COORDINATE WITH OWNER/ENGINEER AND CITY OF MONROE PRIOR TO PERFORMING ANY WORK.
- PRIOR TO WORKING ON PARCEL # 74, CONTRACTOR SHALL CONTACT THE PROPERTY OWNERS REPRESENTATIVES SO TENANTS CAN BE INFORMED OF THE WORK. THE CONTACT INFORMATION IS LISTED BELOW:

JEREMIAH APONTE JAPONTE@INVITATIONHOMES.COM 704-774-0082	AMANDA BLACKMON AMANDA.BLACKMON@INVITATIONHOMES.COM 704-201-3102	ANGELA DEAN ANGELA.DEAN@INVITATIONHOMES.COM 980-253-8183
--	--	--



BLACK & VEATCH
Black & Veatch International Company
Business License No. F-0794
10925 David Taylor Drive, Suite 280
Charlotte, North Carolina 28262

UNION COUNTY PUBLIC WORKS
853W ZONE IMPROVEMENTS
PHASE I TRANSMISSION MAINS

CIVIL
PLAN AND PROFILE
STA 210+00 TO STA 220+00

DESIGNED: MLT, WPS
DETAILED: KTH
CHECKED: CES
APPROVED: SLT
DATE: JANUARY 2021



PROJECT NO.
186110
C21
SHEET
25 OF 42

BID SET

NO.	BY	CHK	APP


REVISIONS AND RECORD OF USE

DATE




- NOTES:**
- REFER TO NOTE 2 ON SHEET A1 FOR UTILITY CONFLICTS INCLUDING BUT NOT LIMITED TO UTILITY POLES, WIRES, AND ANCHORS.
 - EXISTING 10" WATERLINE SHOWN IS BASED OFF GIS AND IS APPROXIMATE. CONTRACTOR SHALL FIELD LOCATE UTILITY AND COORDINATE WITH OWNER/ENGINEER PRIOR TO PERFORMING ANY WORK.
 - CONTRACTOR SHALL REMOVE AND REPLACE TEMPORARY SEDIMENT FENCE PARALLEL TO CREEK OR DRAINAGE SWALE TO PREVENT SEDIMENT RUNOFF INTO THE CREEK OR DRAINAGE SWALE WHEN CONSTRUCTING THE WATERLINE.

PLAN
1" = 40'




PROFILE



FD7005_PW
D10000

NO.	BY	CHK/APP



BLACK & VEATCH
 Black & Veatch International Company
 Business License No. F-0794
 10925 David Taylor Drive, Suite 280
 Charlotte, North Carolina 28262

UNION COUNTY PUBLIC WORKS
 853W ZONE IMPROVEMENTS
 PHASE I TRANSMISSION MAINS
 CIVIL
 PLAN AND PROFILE
 STA 258+00 TO STA 268+00


DESIGNED: MLT, WPS
 DETAILED: KTH
 CHECKED: CES
 APPROVED: SLT
 DATE: JANUARY 2021

0 1/2 1
 IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE

PROJECT NO.
186110

C26
 SHEET
 30 OF 42

BID SET




CONTRACTOR RESPONSIBLE FOR INSPECTING MATERIALS AND WELDS TO INSURE ALL SPIDERS WILL FUNCTION PROPERLY.

CARRIER PIPE	CASING PIPE ID	WALL THICKNESS STREET CROSSINGS	WALL THICKNESS RAILROAD CROSSINGS
4"	8"	0.188"	0.188"
6"	12"	0.188"	0.250"
8"	16"	0.250"	0.281"
10"	16"	0.250"	0.281"
12"	20"	0.281"	0.344"
16"	30"	0.344"	0.375"
24"	30"	0.406"	0.469"
30"	42"	0.500"	0.625"
36"	54"	0.500"	0.781"

NOTES:

- NO PIPE SHALL BE SUPPORTED BY BELL.
- END SECTIONS LESS THAN 4' MAY BE UNSUPPORTED.
- WALL THICKNESS AS PER TABLE UNLESS OTHERWISE SHOWN ON PLAN.
- MASONRY SEAL AT ENDS -- 2" x 4" WEEP HOLE AT LOW END.
- ALL PRESSURE PIPES TO HAVE TRACING WIRE IN ALL CASING BORES.
- GROUT ANNULAR SPACE BETWEEN CARRIER PIPE AND CASING AS SPECIFIED PER NCDOT STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES.

PIPE ENCASEMENT A
NO SCALE




FOR NCDOT ROADWAYS OR COMMERCIAL/INDUSTRIAL DRIVEWAYS, MATCH EXISTING ASPHALT BASE THICKNESS OR PROVIDE 11" ACBC TYPE B 25.0C (WHICHEVER IS GREATER). FOR RESIDENTIAL DRIVEWAYS, MATCH EXISTING ASPHALT BASE THICKNESS OR PROVIDE 6" ACBC TYPE B 25.0C (WHICHEVER IS GREATER).

NOTES:

- MINIMUM DENSITY FOR ALL ASPHALT COURSES SHALL BE 92%.
- ASPHALT CONCRETE SURFACE COURSE (ACSC) SHALL BE PLACED & COMPACTED IN MAXIMUM OF 1.5" LIFTS.
- ASPHALT CONCRETE INTERMEDIATE COURSE (ACIC) SHALL BE PLACED AND COMPACTED IN MAXIMUM OF 4.0" LIFTS.
- ASPHALT CONCRETE BASE COURSE (ACBC) SHALL BE PLACED & COMPACTED IN MAXIMUM OF 4.0" LIFTS.
- SAW CUT EDGES OF CUT TO PROVIDE A SMOOTH, EVEN EDGE FOR THE PATCH, & PREVENT DAMAGE TO THE EXISTING ASPHALT WHICH WILL REMAIN IN PLACE.
- ONLY HALF OF THE ROAD WIDTH SHALL BE OPENED AT ONE TIME IN ORDER TO MAINTAIN TRAFFIC. NO TRENCH SHALL BE LEFT OPEN OVERNIGHT.
- TRAFFIC CONTROL SHALL BE PROVIDED IN ACCORDANCE WITH THE FHWA'S MUTCD.
- BACKFILL TO BE FREE OF ROCKS, FOREIGN MATERIAL OR FROZEN EARTH.
- BACKFILL COMPACTED TO:
 - 95% MAXIMUM DRY DENSITY UNDER ROADS, DRIVEWAYS, SIDEWALKS OR IN AREAS WHERE RESTRAINED JOINTS ARE USED.
 - 95% MAXIMUM DRY DENSITY IN NCDOT RIGHT OF WAY. REFER TO SPECIFICATIONS AND NCDOT ENCROACHMENT AGREEMENTS FOR ADDITIONAL REQUIREMENTS.
- BACKFILL COMPACTED IN MAXIMUM OF 8" LIFTS OVER PIPE & MAXIMUM OF 6" LIFTS AROUND PIPE.
- PATCHES & OVERLAYS:
 - ALL OPEN CUTS IN NCDOT ROADWAYS SHALL BE BACKFILLED, PAVED AND TRAVERSABLE PRIOR TO REMOVING LANE CLOSURE. IN ALL OTHER AREAS, OPEN CUTS SHALL BE PATCHED WITHIN 7 DAYS OF COMPLETION OF THAT PARTICULAR CUT.
 - ALL OPEN CUTS OF NCDOT ROADWAYS SHALL BE OVERLAID 30 DAYS AFTER PAVEMENT REPAIR.
 - WHERE OPEN CUTS RUN ACROSS THE ROADWAY CENTERLINE, THE OVERLAY SHALL BE FROM THE EDGE OF PAVEMENT TO THE EDGE OF PAVEMENT.
 - WHERE OPEN CUTS DO NOT CROSS THE ROADWAY CENTERLINE, THE OVERLAY SHALL BE FROM THE EDGE OF PAVEMENT TO THE ROADWAY CENTERLINE, UNLESS THE ROADWAY CROWN POINT WOULD DICTATE OTHERWISE. REFER TO SPECIFICATIONS AND NCDOT ENCROACHMENT AGREEMENTS FOR ADDITIONAL REQUIREMENTS.
- IF PAVEMENT SETTLEMENT OCCURS, THE CONTRACTOR SHALL REPATCH AT NO ADDITIONAL EXPENSE TO THE OWNERS.
- FOR CITY STREETS, ANY REQUIREMENTS FROM CITY STREET CUT PERMIT SHALL BE FOLLOWED AND MAY SUPERSEDE THIS DETAIL, IF MORE STRINGENT.
- ALL PAVEMENT MARKINGS DISTURBED DURING THE EXECUTION OF THE WORK SHALL BE REPLACED IN ACCORDANCE WITH NCDOT SPECIFICATIONS.
- REFERENCE TO DENSITY BASED ON STANDARD PROCTOR AS DETERMINED BY AASHTO T99 (ASTM D-698).

PAVEMENT REPAIR D
NO SCALE




TYPICAL PIPE CROSSING
A
NO SCALE

NOTES:

- SEE DRAWINGS FOR LOCATION, SIZE AND LENGTH OF STEEL PIPE CASINGS.
- INSTALL DRAINS EACH SIDE OF CARRIER PIPE IN DOWNHILL END WALL.

CASEMENT PIPE UNDER ROAD B
NO SCALE




D	a MIN SOIL		a MIN ROCK	
	in	mm	in	mm
27" (675 mm) & SMALLER	3	75	6	150
30" (750 mm) TO 60" (1500 mm)	4	100	9	225
66" (1650 mm) & LARGER	6	150	12	300


NOTES:

- MINIMUM COVER IS 48".
- SIDEWALL CLEARANCE IS AS NOTED IN MINIMUM TRENCH WIDTH TABLE.
- REFER TO SPECIFICATION SECTION 02202 FOR TRENCHING AND BACKFILL REQUIREMENTS.

WATERLINE TRENCH F
NO SCALE




CONCRETE COLLAR G
NO SCALE



- CONTRACTOR SHALL COMPACT SUB-GRADE TO 100%.
- CONTRACTOR SHALL TO THE NEXT EXPANSION JOINT OR A MINIMUM 5 FEET FROM OUTSIDE TRENCH WALL.

CONCRETE DRIVEWAY REPAIR H
NO SCALE



NOTES:

- VALVE OPERATOR SHALL BE PLACED TO INSURE THAT BLOWOFF DOES NOT GET MAINTENANCE PERSONNEL WET DURING OPERATION.
- EXTEND PIPE ABOVE NORMAL TOP OF CREEK BANK ELEVATION.
- ALL PIPING ABOVE GRADE SHALL BE FACTORY-PRIMED AND FIELD COATED. FIELD COATING SHALL CONSIST OF FIRST COAT EPOXY ENAMEL (7 MILS) AMERON "AMEROCOAT 385 EPOXY", CARBOLINE "890" OR TNEMEC "SERIES 69 HI-BUILD EXPOXOLINE 11" AND FINAL COAT ALIPHATIC POLYURETHANE (7 MILS) AMERON "AMERSHIELD ALIPHATIC POLYURETHANE", CARBOLINE "CARBOTHANE 134 HS", OR TNEMEC "SERIES 74 ENDURASHIELD". THE FINAL COAT SHALL BE ANVIA BLUE IN COLOR.
- TANGENTIAL OUTLET AND BLOW OFF PIPE SIZING SHALL BE AS INDICATED ON PLANS.


BLOW OFF C
NO SCALE

LEGEND


- Bc OUTSIDE DIAMETER OF PIPE
 - H COVER ABOVE TOP OF PIPE
 - D NOMINAL PIPE SIZE
 - a EMBEDMENT BELOW PIPE (SEE TABLE)
- HAND PLACED EMBEDMENT *
 - COMPACTED EMBEDMENT *
 - GRANULAR EMBEDMENT *
 - CONCRETE

NOMINAL PIPE SIZE	MINIMUM TRENCH WIDTH	CLEARANCE
LESS THAN 27 in.	PIPE OD PLUS 24 in.	12 in.
27 in. THROUGH 60 in.	PIPE OD PLUS NOMINAL PIPE SIZE	ID/2
GREATER THAN 60 in.	PIPE OD PLUS 70 in.	30 in.

CLEARANCE = MINIMUM SIDEWALL CLEARANCE; OD = OUTSIDE DIAMETER (OR SPAN) OF CONDUIT; ID = INSIDE DIAMETER (OR SPAN) OF CONDUIT.




GRAVEL DRIVEWAY REPAIR I
NO SCALE



NOTES:

- THE FLUSHING VALVE PORT DIAMETER SHALL BE SIZED ACCORDING TO THE VALVE SIZE.
- EXTEND SS PIPE AS NEEDED TO ALLOW FOR VALVE BOX RISER. SS PIPE SHALL BE SIZED ACCORDING TO FLUSHING PORT DIAMETER.
- 200 PSI RATED SS BALL VALVE SIZED ACCORDING TO FLUSHING PORT DIAMETER.
- EXTEND SUPPORT SLAB 6" BEYOND OUTSIDE SS FLUSHING VALVE END CONNECTION.

BURIED 36" GATE VALVE J
NO SCALE



BLACK & VEATCH
Black & Veatch International Company
Business License No. T-0794
10925 David Taylor Drive, Suite 280
Charlotte, North Carolina 28262

UNION COUNTY PUBLIC WORKS
853W ZONE IMPROVEMENTS
PHASE I TRANSMISSION MAINS


DESIGNED: MLT, WPS
DETAILED: KTH
CHECKED: CES
APPROVED: SLT
DATE: JANUARY 2021

PROJECT NO.
186110

D2
SHEET
36 OF 42


BID SET

F:\0609A
 D:\0000
 PLOTTED: 1/25/2021 1:35 PM FILE: C:\pw_working\cngpw\wd1306238\000.dwg




PROP. PIPELINE OVER EXISTING PIPE PROP. PIPELINE UNDER EXISTING PIPE

CONCRETE CRADLE PROTECTION FOR WATER LINE CROSSINGS
NO SCALE



2" WATER MAIN 2" GATE VALVE - MECHANICAL JOINT 2" BLOW-OFF 2" - 90° BEND




MAINTENANCE: CLEAN OUT SEDIMENT AND DEBRIS AND REPAIR WASH OUTS.

SEE N.C. DEQ EROSION and SEDIMENT CONTROL PLANNING and DESIGN MANUAL FOR CONDITIONS WHERE PRACTICE APPLIES. PLANNING CONSIDERATION & DESIGN CRITERIA.

- NOTES:
1. ENSURE THAT CULVERT ENTRANCES BELOW CHECK DAMS ARE NOT SUBJECT TO DAMAGE OR BLOCKAGE FROM DISPLACED STONES.
 2. THE DRAINAGE AREA IS LIMITED TO ONE HALF ACRE.
 3. KEY THE STONE INTO THE DITCH BANKS AND EXTEND IT BEYOND THE ABUTMENTS A MINIMUM OF 1.5 FEET TO AVOID WASHOUT FROM OVERFLOW AROUND THE DAM.


CHECK DAM
NO SCALE




NOTE: A 27\"/>

TOP BOTTOM (SCREW TYPE) COVER

UNION COUNTY PUBLIC WORKS DEPARTMENT STANDARD DETAIL SCALE: N.T.S. DATE: 11-17-06 1 VALVE BOX




UNION COUNTY PUBLIC WORKS DEPARTMENT STANDARD DETAIL SCALE: N.T.S. DATE: 11-17-06 1A VALVE BOX INSTALLATION



APPROVED SERVICE HARDWARE			
	MUELLER	FORD	
SADDLE	2\"/>	H-13420	S20
BALL CORPORATION	UP TO 8\"/>	SEE NOTE	FC 101
YOKES	B-25008	FB1000G	
ANGLE BALL VALVE	H-5020	Y 502	
CHECK VALVE	B-24273	BAG4-323WG	
CONNECTORS	H-14247-A	HF591-323	
EXPANSION CONNECTION	GRIP JOINT	EC 23	


NOTE: ROMAC 10\"/>

UNION COUNTY PUBLIC WORKS DEPARTMENT STANDARD DETAIL SCALE: N.T.S. DATE: 11-17-06 15 SERVICE CONNECTION



- GENERAL NOTES:
- 1) METER BOX LID TO HAVE AMR LOCATOR (ALLIANCE 1200 OR EQUAL FOR 50W ERT, STANDARD LID FOR 60W ERT)
 - 2) BUILDER/PROPERTY OWNER TO INSTALL NIPPLE, VALVE AND VALVE BOX BEFORE METER WILL BE SET
 - 3) METER AND ERT BY UNION COUNTY @ PREVALING RATE

UNION COUNTY PUBLIC WORKS DEPARTMENT STANDARD DETAIL SCALE: N.T.S. DATE: 1-2-14 6 METER INSTALLATION FOR AMR METERS



UNION COUNTY PUBLIC WORKS DEPARTMENT STANDARD DETAIL SCALE: N.T.S. DATE: 11-17-06 16 THRUST BLOCK

PIPE SIZE	ANCHORAGE SCHEDULE										TEST PRESSURE (P.S.I.)
	11 1/4° BEND		22 1/2° BEND		45° BEND		90° BEND		TEE		
	L	H	L	H	L	H	L	H	L	H	
6"	1'3"	1'0"	2'3"	1'0"	2'6"	1'6"	2'9"	1'6"	2'0"	1'6"	200
	1'6"	1'3"	2'3"	1'6"	3'0"	1'6"	4'0"	1'6"	3'0"	1'6"	300
8"	1'6"	1'6"	2'6"	1'9"	3'0"	2'0"	3'9"	2'0"	2'6"	2'0"	200
	2'0"	1'6"	3'0"	2'0"	3'9"	2'3"	4'6"	2'6"	3'6"	2'3"	300
12"	2'6"	1'9"	4'0"	2'3"	4'3"	3'0"	5'0"	3'3"	4'0"	3'0"	200
	3'6"	2'0"	5'3"	2'6"	6'0"	3'3"	7'0"	3'6"	5'0"	3'6"	300
14"	3'0"	1'0"	4'0"	3'0"	4'6"	3'9"	6'0"	3'9"	4'6"	3'6"	200
	4'0"	2'6"	5'3"	3'6"	6'0"	4'3"	6'6"	5'0"	5'0"	5'0"	300
16"	3'0"	2'9"	4'6"	3'6"	5'0"	4'6"	7'0"	4'3"	5'0"	4'0"	200
	4'0"	3'0"	6'3"	3'9"	6'5"	5'3"	8'0"	5'3"	7'6"	4'0"	300

THRUST BLOCK DIMENSIONS BASED ON SOIL BEARING CAPACITY OF 2000 P.S.F. AND A WATER TEST PRESSURE OF 150 P.S.I. SIZES OF THRUST BLOCKS MAY BE REVISED BY THE ENGINEER WHERE BEARING CAPACITY OF SOIL VARIES.

PROVIDE TAR PAPER JOINT BETWEEN CONCRETE THRUST BLOCK AND PORTION OF PIPE BEING ANCHORED.

ALL CONCRETE THRUST BLOCKS SHALL BE 2500 P.S.I. CONCRETE.


MAXIMUM VERTICAL DEFLECTION SHALL BE 22 1/2\"/>

JOINTS SHALL REMAIN FREE OF CONCRETE FOR INSPECTION, REPAIR OR REPLACEMENT OF JOINTS.

UNION COUNTY PUBLIC WORKS DEPARTMENT STANDARD DETAIL SCALE: N/A DATE: 11-17-06 17 THRUST BLOCK SPECIFICATIONS

P03000A D10000 PLOTTED: 1/25/2021 1:36 PM FILE: C:\pw_working\cngpw\1306238\000.dwg

NO.	BY	CHK	APP
REVISIONS AND RECORD OF USE			
DATE			



BLACK & VEATCH
Black & Veatch International Company
Business License No. F-0794
10925 David Taylor Drive, Suite 280
Charlotte, North Carolina 28262

**UNION COUNTY PUBLIC WORKS
853W ZONE IMPROVEMENTS
PHASE I TRANSMISSION MAINS**
MISCELLANEOUS DETAILS
AND UNION COUNTY STANDARD DETAILS


DESIGNED: MLT, WPS
DETAILED: KTH
CHECKED: CES
APPROVED: SLT
DATE: JANUARY 2021

PROJECT NO. 186110
D4
SHEET 38 OF 42

BID SET


RESTORATIVE PLANTING SCHEDULE		
NO.	SIZE	COMMON NAME
15	15 GAL	MAGNOLIA " BETTY"
11	5 GAL	CRYPTOMERIA JAPONICA
37	5 GAL	NELLY R STEVENS HOLLY

LOT # 36 PLANTING SCHEDULE A
NO SCALE



- NOTES**
- TEMPORARILY RELOCATE EXISTING BUILDINGS AND RESET AS SHOWN.
 - TEMPORARY RELOCATION SITE FOR LARGER BUILDING.
 - INSTALL TEMPORARY DOG FENCING AT THIS LOCATION.
 - INSTALL PERMANENT 6 FT DOG-RUN FENCING WITH GATE AT THIS LOCATION.
 - REMOVE AND RESET WOOD PERIMETER FENCE IN EXISTING LOCATION. REPLACE WITH NEW MATERIAL IF DAMAGE.

LOT # 80 RELOCATION PLAN D
1"=40'



- NOTES:**
- SANDBAG DIKES SHALL BE SITUATED AT THE UPSTREAM AND DOWNSTREAM ENDS OF THE WORK AREA AND STREAM FLOW SHALL BE PUMPED AROUND THE WORK AREA. THE PUMP SHOULD DISCHARGE ONTO A STABLE VELOCITY DISSIPATER CONSTRUCTED OF RIP RAP OR SANDBAGS.
 - WATER FROM THE WORK AREA SHALL BE PUMPED TO A SEDIMENT FILTERING MEASURE SUCH AS A SEDIMENT BAG OR OTHER APPROVED DEVICE. THE MEASURE SHALL BE LOCATED SUCH THAT THE WATER DRAINS BACK INTO THE CHANNEL BELOW THE DOWNSTREAM SANDBAG DIKE WITHOUT CAUSING FURTHER EROSION BETWEEN THE SILT BAG AND STREAM. CONTRACTOR SHALL KEEP AN EXTRA SILT BAG ON SITE AT ALL TIMES DURING CONSTRUCTION.
 - CONTRACTOR SHALL MINIMIZE CREEK BANK DISTURBANCE, CLEARING AND GRUBBING WITHIN CREEK BANKS SHALL BE LIMITED TO THAT REQUIRED BY CONTRACTOR FOR INSTALLATION OF THE PIPELINE.

E TEMPORARY PUMP AROUND
NTS

RESTORATIVE PLANTING SCHEDULE			
NO.	SIZE	COMMON NAME	BOTANICAL NAME
25	15 GAL	CREPE MYRTLE	LAGERSTROEMIA INDICA
5	15 GAL	WHITE OAK	QUERCUS ALBA
5	15 GAL	RED MAPLE	ACER RUBRUM
5	15 GAL	BLACK GUM	NYSSA SYLVATCA
5	15 GAL	AMERICAN ELM	ULMUS AMERICANA
0	15 GAL	WILLOW OAK	QUERCUS PHELLOS
5	15 GAL	SHAGBARK HICKORY	CARYA OVATE

LOT # 52 PLANTING SCHEDULE B
NO SCALE

SEEDING & SEEDBED PREPARATION REQUIREMENTS

DURING CONSTRUCTION THE CONTRACTOR SHALL BE REQUIRED TO CONTROL EROSION ON ALL DISTURBED SLOPES BEFORE THE ESTABLISHMENT OF PERMANENT VEGETATION. TEMPORARY AND PERMANENT SEEDING SHALL BE AS SPECIFIED IN SECTION 02920 OF THE CONTRACT DOCUMENTS AND AS INDICATED BELOW. THE CONTRACTOR SHALL PERFORM MAINTENANCE AS NECESSARY TO KEEP PERMANENT SEEDED AREAS IN A SATISFACTORY CONDITION UNTIL TURNED OVER TO THE CARE OF THE OWNER'S PERSONNEL.

PREPARATION OF SUBSOIL

- COMPLETE OPERATIONS IN THE AREA TO BE SEEDED AND PREPARE SUBSOIL TO ELIMINATE UNEVEN AREAS AND LOW SPOTS. BRING SURFACE TO THE APPROXIMATE DESIGN CONTOURS.
- SCARIFY SUBSOIL TO A DEPTH OF 3 INCHES. REMOVE WEEDS, ROOTS, STONES AND FOREIGN MATERIALS 1-1/2 INCHES IN DIAMETER AND LARGER.

PLACING TOPSOIL

MATERIALS: FERTILE, AGRICULTURAL SOIL, TYPICAL FOR LOCALITY, CAPABLE OF SUSTAINING VIGOROUS PLANT GROWTH, TAKEN FROM DRAINED SITE; FREE OF SUBSOIL, CLAY OR IMPURITIES, PLANTS, WEEDS, AND ROOTS; PH VALUE OF MINIMUM 5.4 AND MAXIMUM OF 7.0.

- PLACE TOPSOIL DURING DRY WEATHER AND ON DRY UNFROZEN SUBSOIL WHERE INDICATED ON DRAWINGS.
- SPREAD TOPSOIL TO A MINIMUM DEPTH OF 4 INCHES. REMOVE VEGETABLE MATTER AND FOREIGN NON-ORGANIC MATERIAL FROM TOPSOIL WHILE SPREADING. GRADE SURFACE TO PROVIDE POSITIVE DRAINAGE AND PREVENT WATER PONDING. LIGHTLY COMPACT TOPSOIL WITH AT LEAST ONE PASS OF A CULTIPACKER OR SIMILAR EQUIPMENT
- MAINTAIN THE FINISHED SURFACES BY PROTECTING, AND REPLACING TOPSOIL AND SUBSOIL AS NECESSARY UNTIL THE AREA IS ACCEPTED UNDER THE CONTRACT.

APPLICATION OF LIME

MATERIALS: GROUND DOLOMITIC AGRICULTURAL LIMESTONE, NOT LESS THAN 85 PERCENT TOTAL CARBONATES, GROUND SO THAT 50 PERCENT PASSES 100 MESH SIEVE AND 90 PERCENT PASSES 30 MESH SIEVE. COARSER MATERIAL WILL BE ACCEPTABLE, PROVIDED THE SPECIFIED RATES OF APPLICATION ARE INCREASED PROPORTIONATELY ON THE BASIS OF QUANTITIES PASSING NO. 100 MESH SIEVE.

- LIMING SHALL BE DONE IMMEDIATELY AFTER GRADING HAS REACHED THE FINE GRADING STAGE, EVEN THOUGH ACTUAL SEEDING MAY NOT BE DONE UNTIL SEVERAL MONTHS LATER.
- SPREAD LIME EVENLY BY MEANS OF A MECHANICAL DISTRIBUTOR.
- WHEN LIME IS DISTRIBUTED BY COMMERCIAL LIMING DEALERS, SALES SLIPS SHOWING THE TONNAGE DELIVERED SHALL BE FILED WITH THE ENGINEER AND SHALL SHOW THE FULL TONNAGE REQUIRED FOR THE ACRES TREATED.
- INCORPORATE LIME IN THE TOP 2 TO 3 INCHES OF SOIL BY HARROWING, DISKING, OR OTHER APPROVED MEANS. LIME SHALL BE APPLIED AT A MINIMUM OF 2 TONS PER ACRE WITH 3 TONS PER ACRE IN CLAY SOILS OR PER SOILS TEST.

APPLICATION OF FERTILIZER

MATERIALS: FERTILIZER: MIXED, COMMERCIAL, FERTILIZER CONTAINING 10-10-10 PERCENTAGES OF AVAILABLE NITROGEN, PHOSPHORIC ACID, AND POTASH RESPECTIVELY, PLUS SUPERPHOSPHATE WITH 20 PERCENT P205 CONTENT. FERTILIZER SHALL BE DRY, IN GRANULAR (PELLET) FORM, SHALL BE DELIVERED TO THE SITE IN THE MANUFACTURER'S ORIGINAL BAG OR CONTAINER WHICH SHALL BE PLAINLY MARKED AS TO FORMULA.

- SPREAD FERTILIZER NOT MORE THAN 2 WEEKS IN ADVANCE OF SEEDING.
- TO VERIFY APPLICATION RATE, DETERMINE ACREAGE TO BE FERTILIZED AND PROVIDE ENGINEER WITH TOTAL WEIGHT OF FERTILIZER APPLIED TO THE AREA.
- PROVIDE MECHANICAL SPREADER FOR EVEN DISTRIBUTION AND SPREAD HALF OF THE RATE IN ONE DIRECTION, AND THE OTHER HALF AT RIGHT ANGLES TO THE FIRST. MIX THOROUGHLY INTO UPPER 2 TO 3 INCHES OF SOIL BY DISKING, HARROWING OR OTHER APPROVED METHODS.

SEEDING

MATERIALS: SEED: FRESH SEED GUARANTEED 95 PERCENT PURE WITH A MINIMUM GERMINATION RATE OF 85 PERCENT WITHIN ONE YEAR OF TESTS. PROVIDE THE FOLLOWING SEED MIXTURES WITH LIME AND FERTILIZER IN DISTURBED AREAS INCLUDING NCDOT RIGHTS-OF-WAY:

1. TEMPORARY SEEDING

TEMPORARY SEEDING		
PLANTING DATES	GRASS TYPE	POUNDS/ACRE
JAN 1 - MAY 1	RYE (GRAIN)	120
MAY 1 - AUG 15	GERMAN MILLET	50
AUG 15 - DEC 30	RYE (GRAIN)	120
LIME		2,000
FERTILIZER (JAN 1 - AUG 15)	10-10-10	750
FERTILIZER (AUG 15 - DEC 30)	10-10-10	1,000
MULCH	STRAW	4,000

2. PERMANENT SEEDING (MAXIMUM SLOPE 3:1)

PERMANENT SEEDING (MAXIMUM SLOPE 3:1)		
PLANTING DATES	GRASS TYPE	POUNDS/ACRE
AUG. 15 - NOV. 1	TALL FESCUE	300
NOV. 1 - MAR. 1	TALL FESCUE	300
&	ABRUZZI RYE	25
MAR. 1 - APR 15	TALL FESCUE	300
APR. 15 - JUN. 30	HULLED COMMON	25
	BERMUDA GRASS	
JUL. 1 - AUG. 15	TALL FESCUE	120
&	BROWNTOP MILLET	35
&	SORGHUM-SUDAN HYBRIDS	30
LIME		4,000
FERTILIZER	10-10-10	1,000
MULCH	STRAW	4,000

RESTORATIVE PLANTING SCHEDULE			
NO.	SIZE	COMMON NAME	BOTANICAL NAME
11	15 GAL	RED MAPLE	ACER RUBRUM
10	15 GAL	WHITE OAK	QUERCUS ALBA
4	15 GAL	OKAME CHERRY	PRUNUS X INCAM
3	15 GAL	JAPANESE RED MAPLE	ACER PALMATUM
2	15 GAL	NATCHEZ CREPE MYRTLE	LAGERSTROEMIA NATCHEZ

LOT # 53/54 PLANTING SCHEDULE C
NO SCALE

SEEDING & SEEDBED PREPARATION REQUIREMENTS (CON'T)

3. PERMANENT SEEDING (MAXIMUM SLOPE 3:1 TO 2:1)

PERMANENT SEEDING (MAXIMUM SLOPE 3:1 TO 2:1)		
PLANTING DATES	GRASS TYPE	POUNDS/ACRE
MAR. 1 - JUN. 1	SERICEA LESPEDEZA	50
	&	
MAR. 1 - APR. 15	ADD TALL FESCUE	120
MAR. 1 - JUN 30 OR	ADD HULLED COMMON	25
	BERMUDAGRASS	
JUL. 1 - SEPT. 1	TALL FESCUE	120
&	BROWNTOP MILLET	35
&	SORGHUM-SUDAN HYBRIDS	30
SEPT. 1 - MAR. 1	SERICEA LESPEDEZA	70
	UNHULLED-UNSCARIFIED)	
&	TALL FESCUE	120
	&	
NOV. 1 - MAR. 1	ADD ABRUZZI RYE	25
LIME		4,000
FERTILIZER	10-10-10	1,000
MULCH	STRAW	4,000

- THE CONTRACTOR SHALL PROVIDE SEEDING AND FOLLOW FERTILIZING METHODS AS REQUIRED BY THE U.S. ARMY CORPS OF ENGINEERS TO REESTABLISH DISTURBED AREAS IN DESIGNATED WETLANDS.
- ACCOMPLISH SEEDING BY MEANS OF AN APPROVED POWER-DRAWN SEED DRILL, COMBINATION CORRUGATED ROLLER-SEEDER, APPROVED HAND OPERATED MECHANICAL SEEDER, OR OTHER APPROVED METHODS TO PROVIDE EVEN DISTRIBUTION OF SEED.
- DO NOT SEED WHEN GROUND IS EXCESSIVELY WET OR EXCESSIVELY DRY. AFTER SEEDING, ROLL AREA WITH A ROLLER, NOT LESS THAN 18 INCHES IN DIAMETER AND WEIGHING NOT MORE THAN 210 POUNDS PER FOOT OF WIDTH. UPON COMPLETION OF ROLLING, WATER AREA WITH A FINE SPRAY.
- IMMEDIATELY FOLLOWING SEEDING APPLY MULCH OR MATTING AS LISTED BELOW. DO NOT SEED AREAS IN EXCESS OF THAT WHICH CAN BE MULCHED ON SAME DAY.
- APPLY WATER WITH A FINE SPRAY IMMEDIATELY AFTER EACH AREA HAS BEEN MULCHED. SATURATE TO 4 INCHES OF SOIL DEPTH.
- WETLAND SEEDING.


WETLAND SEEDING		
PLANTING DATES	GRASS TYPE	POUNDS/ACRE
AUG 15 - APR 15	RYE (GRAIN)	40
MAY 1 - AUG 15	GERMAN MILLET	10
DEC 1 - APR 1	SWEET WOODREED	2.5
DEC 1 - APR 1	RICE CUTGRASS	6.0
DEC 1 - MAY 15 & SEPT 1 - NOV 1	SOFT RUSH	2.5
DEC 1 - MAY 15 & SEPT 1 - NOV 1	SHALLOW SEDGE	2.5
LIME		PER SOIL TEST
FERTILIZER	10-10-10	PER SOIL TEST
MULCH	STRAW	4,000

MULCHING AND MATTING

MATERIALS: MATTING / EROSION CONTROL FABRIC (RECP); MATTING AND RECP SHALL BE AS NOTED ON DETAIL F ON SHEET D1. MATTING SHALL BE FULLY DEGRADABLE BUT SUITABLE UNTIL VEGETATION HAS BEEN ESTABLISHED.

MATERIALS: MULCH: THRESHED STRAW OF OATS, WHEAT, OR RYE; FREE FROM SEED OF OBNOXIOUS WEEDS; OR CLEAN SALT HAY. STRAW WHICH IS FRESH AND EXCESSIVELY BRITTLE OR STRAW WHICH IS IN SUCH AN ADVANCED STAGE OF DECOMPOSITION AS TO SMOOTH OR RETARD GROWTH OF GRASS WILL NOT BE ACCEPTABLE.


- APPLY MULCH OR MATTING AS REQUIRED TO RETAIN SOIL AND GRASS, BUT NO LESS THEN THE FOLLOWING:
 - SLOPES FROM 0 TO 20 PERCENT BY SPREADING A LIGHT COVER OF MULCH OVER SEEDED AREA AT THE RATE OF NOT LESS THAN 85 LBS. PER 1000 SQ. FT. USE TACK TO PREVENT DISRUPTION OF MULCH.
 - SLOPES GREATER THAN 20 PERCENT MULCH WITH MATTING. PIN MATTING TO THE GROUND WITH WIRE STAPLES AT 5 FOOT INTERVALS, IMMEDIATELY AFTER SEEDING.
- FOR TACK USE AN ASPHALT TIE-DOWN OF EMULSIFIED ASPHALT GRADE AE-3 OR CUT-BACK ASPHALT GRADE RC-2 OR OTHER APPROVED EQUAL. THE APPLICATION RATE SHALL BE 0.10 GAL/SY (11 GAL / 1000 SQ FT). AN APPROVED JUTE MESH OR NET MAY BE USED IN LIEU OF TACKING STRAW MULCH.
- OTHER TYPES OF MULCH AND ANCHORING METHODS MAY BE USED UPON APPROVAL BY THE ENGINEER.



BLACK & VEATCH
Black & Veatch International Company
Business License No. F-0794
10925 David Taylor Drive, Suite 280
Charlotte, North Carolina 28262

UNION COUNTY PUBLIC WORKS
853W ZONE IMPROVEMENTS
PHASE I TRANSMISSION MAINS
RESTORATIVE PLANTING
DETAILS AND SCHEDULES

DESIGNED: MLT
DETAILED: KTH
CHECKED: CES
APPROVED: SLT
DATE: JANUARY 2021



PROJECT NO.
186110

D6
SHEET
40 OF 42

BID SET

**PART III
SELF-INSPECTION, RECORDKEEPING AND REPORTING**

SECTION A: SELF-INSPECTION

Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record.

Inspect	Frequency (during normal business hours)	Inspection records must include:
(1) Rain gauge maintained in good working order	Daily	Daily rainfall amounts. If no daily rain gauge observations are made during weekend or holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those unattended days (and this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device approved by the Division.
(2) E&SC Measures	At least once per 7 calendar days and within 24 hours of a rain event \geq 1.0 inch in 24 hours	1. Identification of the measures inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Indication of whether the measures were operating properly, 5. Description of maintenance needs for the measure, 6. Description, evidence, and date of corrective actions taken.
(3) Stormwater discharge outfalls (SDOs)	At least once per 7 calendar days and within 24 hours of a rain event \geq 1.0 inch in 24 hours	1. Identification of the discharge outfalls inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, 5. Indication of visible sediment leaving the site, 6. Description, evidence, and date of corrective actions taken.
(4) Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event \geq 1.0 inch in 24 hours	If visible sedimentation is found outside site limits, then a record of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has left the site limits, 2. Description, evidence, and date of corrective actions taken, and 3. An explanation as to the actions taken to control future releases.
(5) Streams or wetlands onsite or offsite (where accessible)	At least once per 7 calendar days and within 24 hours of a rain event \geq 1.0 inch in 24 hours	If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit of this permit.
(6) Ground stabilization measures	After each phase of grading	1. The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover). 2. Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement.

**PART III
SELF-INSPECTION, RECORDKEEPING AND REPORTING**

SECTION B: RECORDKEEPING

1. E&SC Plan Documentation

The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be documented in the manner described:

Item to Document	Documentation Requirements
(a) Each E&SC Measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC Plan.	Initial and date each E&SC Measure on a copy of the approved E&SC Plan or complete, date and sign an inspection report that lists each E&SC Measure shown on the approved E&SC Plan. This documentation is required upon the initial installation of the E&SC Measures or if the E&SC Measures are modified after initial installation.
(b) A phase of grading has been completed.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(c) Ground cover is located and installed in accordance with the approved E&SC Plan.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
(d) The maintenance and repair requirements for all E&SC Measures have been performed.	Complete, date and sign an inspection report.
(e) Corrective actions have been taken to E&SC Measures.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate the completion of the corrective action.

2. Additional Documentation

In addition to the E&SC Plan documents above, the following items shall be kept on the site

and available for agency inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:

- (a) This general permit as well as the certificate of coverage, after it is received.
- (b) Records of inspections made during the previous 30 days. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.
- (c) All data used to complete the Notice of Intent and older inspection records shall be maintained for a period of three years after project completion and made available upon request. [40 CFR 122.41]

**PART III
SELF-INSPECTION, RECORDKEEPING AND REPORTING**

SECTION C: REPORTING

1. Occurrences that must be reported

Permittees shall report the following occurrences:

- (a) Visible sediment deposition in a stream or wetland.
- (b) Oil spills if:
 - They are 25 gallons or more,
 - They are less than 25 gallons but cannot be cleaned up within 24 hours,
 - They cause sheen on surface waters (regardless of volume), or
 - They are within 100 feet of surface waters (regardless of volume).
- (a) Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85.
- (b) Anticipated bypasses and unanticipated bypasses.
- (c) Noncompliance with the conditions of this permit that may endanger health or the environment.

2. Reporting Timeframes and Other Requirements

After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Division's Emergency Response personnel at (800) 662-7956, (800) 858-0368 or (919) 733-3300.

Occurrence	Reporting Timeframes (After Discovery) and Other Requirements
(a) Visible sediment deposition in a stream or wetland	<ul style="list-style-type: none"> • Within 24 hours, an oral or electronic notification. • Within 7 calendar days, a report that contains a description of the sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis. • If the stream is named on the NC 303(d) list as impaired for sediment-related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliance with the federal or state impaired-waters conditions.
(b) Oil spills and release of hazardous substances per Item 1(b)-(c) above	<ul style="list-style-type: none"> • Within 24 hours, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and location of the spill or release.
(c) Anticipated bypasses [40 CFR 122.41(m)(3)]	<ul style="list-style-type: none"> • A report at least ten days before the date of the bypass, if possible. The report shall include an evaluation of the anticipated quality and effect of the bypass.
(d) Unanticipated bypasses [40 CFR 122.41(m)(3)]	<ul style="list-style-type: none"> • Within 24 hours, an oral or electronic notification. • Within 7 calendar days, a report that includes an evaluation of the quality and effect of the bypass.
(e) Noncompliance with the conditions of this permit that may endanger health or the environment [40 CFR 122.41(l)(7)]	<ul style="list-style-type: none"> • Within 24 hours, an oral or electronic notification. • Within 7 calendar days, a report that contains a description of the noncompliance, and its causes; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time noncompliance is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. [40 CFR 122.41(l)(6). • Division staff may waive the requirement for a written report on a case-by-case basis.

NCG01 SELF-INSPECTION, RECORDKEEPING AND REPORTING

EFFECTIVE: 04/01/19

BID SET



BLACK & VEATCH
Black & Veatch International Company
Business License No. P-0794
10925 Daniel Taylor Drive, Suite 280
Charlotte, North Carolina 28262

**UNION COUNTY PUBLIC WORKS
853W ZONE IMPROVEMENTS
PHASE I TRANSMISSION MAINS**

NCG01 SELF-INSPECTION
RECORDKEEPING AND REPORTING

DESIGNED: MLT, WPS
DETAILED: KTH
CHECKED: CES
APPROVED: SLT
DATE: JANUARY 2021

0 1/2 1
IF THIS BAR DOES NOT
MEASURE 1" THEN DRAWING
IS NOT TO FULL SCALE

PROJECT NO.
186110

**D7
SHEET
41 OF 42**

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT

Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

SECTION E: GROUND STABILIZATION

Required Ground Stabilization Timeframes		
Site Area Description	Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations
(a) Perimeter dikes, swales, ditches, and perimeter slopes	7	None
(b) High Quality Water (HQW) Zones	7	None
(c) Slopes steeper than 3:1	7	If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed
(d) Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed
(e) Areas with slopes flatter than 4:1	14	-7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed unless there is zero slope

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

GROUND STABILIZATION SPECIFICATION

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:

Temporary Stabilization	Permanent Stabilization
<ul style="list-style-type: none"> Temporary grass seed covered with straw or other mulches and tackifiers Hydroseeding Rolled erosion control products with or without temporary grass seed Appropriately applied straw or other mulch Plastic sheeting 	<ul style="list-style-type: none"> Permanent grass seed covered with straw or other mulches and tackifiers Geotextile fabrics such as permanent soil reinforcement matting Hydroseeding Shrubs or other permanent plantings covered with mulch Uniform and evenly distributed ground cover sufficient to restrain erosion Structural methods such as concrete, asphalt or retaining walls Rolled erosion control products with grass seed

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS

- Select flocculants that are appropriate for the soils being exposed during construction, selecting from the *NC DWR List of Approved PAMS/Flocculants*.
- Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
- Apply flocculants at the concentrations specified in the *NC DWR List of Approved PAMS/Flocculants* and in accordance with the manufacturer's instructions.
- Provide ponding area for containment of treated Stormwater before discharging offsite.
- Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

EQUIPMENT AND VEHICLE MAINTENANCE

- Maintain vehicles and equipment to prevent discharge of fluids.
- Provide drip pans under any stored equipment.
- Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.
- Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
- Remove leaking vehicles and construction equipment from service until the problem has been corrected.
- Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

- Never bury or burn waste. Place litter and debris in approved waste containers.
- Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes.
- Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.
- Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.
- Anchor all lightweight items in waste containers during times of high winds.
- Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.
- Dispose waste off-site at an approved disposal facility.
- On business days, clean up and dispose of waste in designated waste containers.

PAINT AND OTHER LIQUID WASTE


- Do not dump paint and other liquid waste into storm drains, streams or wetlands.
- Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Contain liquid wastes in a controlled area.
- Containment must be labeled, sized and placed appropriately for the needs of site.
- Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

PORTABLE TOILETS

- Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
- Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas.
- Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

EARTHEN STOCKPILE MANAGEMENT

- Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably available.
- Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
- Provide stable stone access point when feasible.
- Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.



CONCRETE WASHOUTS

- Do not discharge concrete or cement slurry from the site.
- Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.
- Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.
- Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
- Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.
- Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.
- Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.
- Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location.
- Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
- At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

HERBICIDES, PESTICIDES AND RODENTICIDES

- Store and apply herbicides, pesticides and rodenticides in accordance with label restrictions.
- Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.
- Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.
- Do not stockpile these materials onsite.

HAZARDOUS AND TOXIC WASTE


- Create designated hazardous waste collection areas on-site.
- Place hazardous waste containers under cover or in secondary containment.
- Do not store hazardous chemicals, drums or bagged materials directly on the ground.



BLACK & VEATCH
 Black & Veatch International Company
 Business License No. F-0794
 10925 David Taylor Drive, Suite 280
 Charlotte, North Carolina 28262

UNION COUNTY PUBLIC WORKS
 853W ZONE IMPROVEMENTS
 PHASE I TRANSMISSION MAINS
 NCG01 GROUND STABILIZATION
 AND MATERIALS HANDLING

DESIGNED: MLT, WPS
 DETAILED: KTH
 CHECKED: CES
 APPROVED: SLT
 DATE: JANUARY 2021



PROJECT NO.
 186110

D8
 SHEET
 42 OF 42

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

BID SET