GENERAL NOTES

PRIOR TO DIGGING.

- 1. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE TECHNICAL SPECIFICATIONS AND ALL APPLICABLE PERMITS.
- 2. LOCATION SHOWN FOR UNDERGROUND UTILITIES AND STRUCTURES ARE BASED ON FIELD SURVEYS AND RECORD DRAWINGS AND ARE SHOWN FOR GENERAL INFORMATION ONLY. THESE LOCATIONS SHOULD BE CONSIDERED APPROXIMATE AND SHALL BE FIELD VERIFIED BY THE CONTRACTOR IN ADVANCE OF THE WORK, BOTH HORIZONTALLY AND VERTICALLY, TO DETERMINE EXACT SIZE, MATERIAL, DEPTH, LOCATION, AND OTHER UTILITIES NOT SHOWN. EXISTING UTILITY CROSSING AND CONFLICTS SHALL BE COORDINATED WITH UTILITY OWNER AT NO ADDITIONAL COST TO THE CLIENT. CALL THE LOCAL PUBLIC UTILITIES LOCATING SERVICE AT LEAST 72 HOURS PRIOR TO DIGGING FOR LOCATION ASSISTANCE. CONTRACTOR IS RESPONSIBLE FOR CONTACTING ALL UTILITIES
- 3. WHEN NEW LINE IS WITHIN FIVE FEET OF EXISTING UTILITIES, CONTRACTOR SHALL DIG TEST PITS TO LOCATE EXISTING LINES IN ADVANCE OF PIPE LAYING OPERATIONS TO ALLOW ADEQUATE TIME FOR ANY NECESSARY RE-ALIGNMENTS OR ADJUSTMENTS.
- 4. PROVIDE POWER POLE SUPPORT WHEN OPEN DITCH IS WITHIN 5'-0" OF POLE AND WHEN OWNER AND/OR CONDITIONS WARRANT. COORDINATE WITH POWER UTILITY. ADDITIONAL POLES NOT SPECIFICALLY SHOWN MAY ALSO REQUIRE TEMPORARY SUPPORT IF EXCAVATION IS WITHIN 5' OF POLES.
- 5. ALL ITEMS SUCH AS: FENCES, STORM DRAINS, MAIL BOXES, SIGNS, UNDERGROUND CABLE, PROPERTY PINS, LANDSCAPED SHRUBBERY, ETC., THAT NEED TO BE REMOVED FOR CONSTRUCTION AND REPLACED SHALL BE PROTECTED AND RE-INSTALLED TO THE SATISFACTION OF THE OWNER. CONTRACTOR SHALL RE-ESTABLISH A TEMPORARY RELOCATION IMMEDIATELY AND IN NO CASE LONGER THAN BY THE END OF EACH WORK DAY. CONTRACTOR SHALL COORDINATE WITH PROPERTY OWNERS AS NECESSARY FOR ITEMS SUCH AS FENCES THAT MUST BE MAINTAINED FOR CONTROL OF LIVESTOCK OR SECURITY. TEMPORARY FENCE LINES, ETC., SHALL BE INSTALLED AT NO ADDITIONAL COST TO THE OWNER.
- 6. PIPELINE SHALL HAVE A MINIMUM COVER OF 3'-6"
 (UNLESS NOTED OTHERWISE) AND LAID TO AVOID AIR
 POCKETS ALONG THE TOP OF PIPE. CONTRACTOR
 SHALL PERFORM HIS OWN GROUND SURVEY PRIOR TO
 PIPE INSTALLATION TO VERIFY GRADES AND
 ELEVATIONS.
- 7. ALL AIR RELEASE VALVES TO BE PLACED AT HIGH SPOT OF PIPELINE AT STATIONS INDICATED PLUS OR MINUS ONE PIPE JOINT.
- 8. PIPE DEFLECTIONS NOT EXCEED MAXIMUM ONE-HALF OF MANUFACTURER'S RECOMMENDED DEFLECTION ANGLE.
- 9. ALL AREAS DISTURBED BEYOND THE LIMITS OF CONSTRUCTION SHALL BE RESTORED REGARDLESS OF AREA AFFECTED AT NO ADDITIONAL COST TO THE OWNER.
- 10. ALL AIR RELEASE VALVES ARE TO BE INSTALLED AT LOCATIONS SHOWN +/- ONE PIPE JOINT IN ORDER TO ENSURE INSTALLATION AT HIGH/LOW POINTS RESPECTIVELY. ALL OTHER VALVES AND BENDS SHALL BE INSTALLED AT LOCATIONS INDICATED +/- 3'-0".
- 11. ALL RESTRAINED JOINT LENGTHS ARE MINIMUM DISTANCES REQUIRED FROM AN APPLICABLE BEND/APPURTENANCE. ALL FITTINGS INSTALLED WITHIN RESTRAINED LENGTHS INDICATED SHALL BE RESTRAINED.
- 12. CONTRACTOR SHALL INSTALL PIPELINES AND APPURTENANCES IN LOCATIONS AND AT GRADES INDICATED. CONTRACTOR TO MAKE MINOR ALIGNMENT CHANGES AND DEFLECT PIPE WITHIN ACCEPTABLE DEFLECTIONS TO GENERALLY FOLLOW LAYOUT INDICATED.
- 13. CONTRACTOR SHALL CLEAR AND GRUB RIGHT OF WAY AND TEMPORARY CONSTRUCTION EASEMENT AS NECESSARY TO COMPLETE INSTALLATION OF PIPELINE.
- 14. INSIDE/ALONG ROADWAY RIGHTS-OF-WAY,
 CONTRACTOR SHALL DISTURB AND RESTORE AREAS
 NECESSARY FOR CONSTRUCTION IN ACCORDANCE
 WITH APPROVED SCDOT ENCROACHMENT PERMIT.
 LIMITS OF CONSTRUCTION EXTEND TO ROADWAY
 PAVEMENT AS NECESSARY. ALL CONSTRUCTION
 ACTIVITIES SHALL BE CONTAINED WITHIN
 ESTABLISHED EASEMENTS AND RIGHT OF WAYS
 SHOWN ON THE CONSTRUCTION DRAWINGS.
- 15. WHEN FIELD CUTS OF PIPE ARE NECESSARY THE CONTRACTOR SHALL CUT PIPE WITH A PIPE SAW IN ACCORDANCE WITH APPLICABLE AWWA REQUIREMENTS. FIELD WELDING OR TORCH-CUTTING ARE PROHIBITED ON THIS CONTRACT.

16. CONTRACTOR SHALL SAW-CUT EXISTING PAVEMENT FOR ALL ASPHALT DRIVES/ROADS AND RESTORE PAVEMENT IN ACCORDANCE WITH SPECIFICATIONS AND DETAIL 1/C900.

WETLANDS REQUIREMENTS

- 1. THERE SHALL BE NO DISTURBANCE TO THE WETLANDS AREAS EXCEPT AS INDICATED ON PLANS AND IN THE UNITED STATES ARMY CORPS OF ENGINEERS NATIONWIDE 12 PERMIT.
- 2. CONTRACTOR SHALL INSTALL SEDIMENT CONTROL FENCES TO BORDER LIMITS OF DISTURBANCE, AS SHOWN. INSTALL DOUBLE ROW OF SILT FENCE WHERE INDICATED.
- 3. ANY DEWATERING WILL BE DISCHARGED EITHER INTO A SEDIMENTATION DEVICE OR A SEDIMENT FILTER BAG PRIOR TO DISCHARGE.
- 4. THE CONTRACTOR SHALL STABILIZE THE DISTURBED AREAS ADJACENT TO WETLANDS AND WATERS OF THE STATE IMMEDIATELY FOLLOWING INSTALLATION.

ADDITIONAL REQUIREMENTS FOR WORK INSIDE OF SCDOT RIGHT-OF-WAY

- 1. CONTRACTOR SHALL PROVIDE SCDOT WITH A DETAILED TRAFFIC CONTROL PLAN FOR ALL WORK WITHIN SCDOT RIGHT-OF-WAY THAT COMPLIES WITH THE SCDOT MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES FOR STREETS AND HIGHWAYS, LATEST EDITION, AND EXECUTE TRAFFIC CONTROLS IN ACCORDANCE WITH SCDOT APPROVED TRAFFIC CONTROL PLAN. THE TRAFFIC CONTROL PLAN SHALL BE SUBMITTED TO SCDOT A MINIMUM OF SEVEN DAYS PRIOR TO THE WORK REQUIRING TRAFFIC CONTROL. ALL WORK WITHIN THE PUBLIC HIGHWAY RIGHT-OF-WAY SHALL BE IN STRICT ACCORDANCE WITH THE SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION (SCDOT) ENCROACHMENT PERMIT AND IN ACCORDANCE WITH THE APPROVED TRAFFIC CONTROL PLAN.
- 2. INSTALL TRAFFIC CONTROL AND SAFETY MEASURES AS NEEDED IN ACCORDANCE WITH SCDOT REQUIREMENTS. TRAFFIC CONTROL DEVICES TO BE MAINTAINED THROUGHOUT THE PROJECT DURATION AS REQUIRED. LANE CLOSURES SHALL BE IN ACCORDANCE WITH SCDOT PERMIT. TRAFFIC CONTROL STANDARDS MUST BE ADHERED TO ON ALL LOCATIONS WITHIN SCDOT'S RIGHT-OF-WAY.
- 3. ALL EROSION CONTROL, CLEARING, GRUBBING, INSTALLATION AND RESTORATION TO BE IN ACCORDANCE WITH SPECIFICATIONS AND DRAWINGS.
- 4. TEMPORARILY STORE AND REMOVE SOILS IN SUCH A WAY TO PROTECT EXISTING ROAD PAVEMENT.
- 5. ALL FILL MATERIAL PLACED SHALL BE IN ACCORDANCE WITH SCDOT REQUIREMENTS.
- 6. FINISH GRADE SWALES. FERTILIZE AND SEED DISTRUBED AREAS. RELOCATE AND REPLACE ALL SEDIMENT AND EROSION CONTROL MEASURES AT END OF EACH DAY. ALL SLOPES 2:1 OR GREATER SHALL RECEIVE PERMANENT EROSION CONTROL MATTING OR HYDROSEEDING.
- 7. ALL BACKFILL IN SCDOT RIGHT-OF-WAY SHALL MEET MINIMUM LIFT REQUIREMENTS OF 6 INCHES WHEN COMPACTED.
- 8. ALL PIPE MARKERS IN SCDOT ROW SHALL BE FIBERGLASS AS APPROVED BY SCDOT.
- 9. FOR ALL DITCHES WITHIN THE SCDOT RIGHT-OF-WAY THAT HAVE SIDELINE GRADES DISTURBED, THE DITCH SHOULD BE REPAIRED IN ACCORDANCE WITH DETAIL 0227011 AND AS SHOWN ON PLANS.
- 10. ALL STORM DRAIN INSTALLATIONS AND REPAIRS, IF APPLICABLE, SHALL COMPLY WITH SCDOT STANDARD SPECIFICATIONS AND DRAWINGS.
- 11. ROAD CONSTRUCTION SIGNS SHALL BE UTILIZED AND MAINTAINED PROPERLY IN ACCORDANCE WITH SCDOT STANDARD SPECIFICATIONS AND DRAWINGS.
- 12. THE PROJECT LIMITS ALONG CLEMENTS FERRY ROAD MAY CONTAIN HEADWALLS, STORM DRAIN PIPES, LANDSCAPING AND ETC. THE CONTRACTOR SHALL ADDRESS ANY DISTURBANCE TO THESE ITEMS WITH SCDOT AND/OR PROPERTY OWNERS PRIOR TO CONSTRUCTION.

SEQUENCE OF CONSTRUCTION OPERATIONS 1. NO WORK TO BE PERFORMED PRIOR TO RECEIPT OF

- NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) COVERAGE FROM SCDHEC.
- 2. CONTRACTOR TO SCHEDULE A PRE-CONSTRUCTION MEETING PRIOR TO ANY COMMENCEMENT OF WORK.
- . CONTRACTOR SHALL SIGN AND IMPLEMENT THE REQUIREMENTS OF THE APPROVED STORMWATER POLLUTION PREVENTION PLAN (SWPPP) AND CONTACT THE SCDHEC REGIONAL EA OFFICE LISTED BELOW PRIOR TO STARTING ANY LAND-DISTURBING ACTIVITIES. THE CONTRACTOR SHALL ABIDE BY ALL REQUIREMENTS OF THE SOUTH CAROLINA NPDES GENERAL PERMIT FOR STORMWATER DISCHARGES FROM CONSTRUCTION ACTIVITIES SCR100000. THE SWPPP AND ALL REQUIRED DOCUMENTATION SHALL BE KEPT UP TO DATE AND MAINTAINED IN A SAFE LOCATION ON-SITE AT ALL TIMES DURING CONSTRUCTION.
 - LOWCOUNTRY EA CHARLESTON 1362 McMILLAN AVENUE, SUITE 300 CHARLESTON, SC 29405 (843) 953-0150
- 4. INSTALL PHASE ONE EROSION AND SEDIMENTATION CONTROL MEASURES AS SHOWN ON THE CONTRACT DRAWINGS. NO CONSTRUCTION OR LAND DISTURBANCE ACTIVITIES MAY BEGIN UNTIL ALL EROSION AND SEDIMENTATION CONTROL MEASURES HAVE BEEN INSTALLED AROUND CONSTRUCTION AREAS. IF CLEARING IS REQUIRED FOR INSTALLATION OF A GIVEN MEASURE, ALL OTHER MEASURES SHOWN SHALL BE INSTALLED FIRST. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS BETWEEN THE DISTURBED AREA AND ALL WATERS OF THE STATE (WoS). A 10-FOOT BUFFER SHALL BE MAINTAINED WHERE POSSIBLE BETWEEN THE SILT FENCE AND THE WoS.
- 5. ONCE ALL PHASE ONE MEASURES HAVE BEEN INSTALLED, THE SITE SHALL BE CLEARED AND GRUBBED AS SHOWN ON THE CONTRACT DRAWINGS. CONTRACTOR LAYDOWN/STOCKPILE/CONCRETE WASHOUT AREAS SHALL BE LOCATED AS SHOWN ON THE CONTRACT DRAWINGS.
- 6. UPON COMPLETION OF CLEARING AND GRUBBING, PHASE TWO EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSTALLED.
- 7. ONCE ALL PHASE TWO MEASURES HAVE BEEN INSTALLED, CONSTRUCTION ACTIVITIES MAY BEGIN. ONLY THE LENGTH OF TRENCH IN WHICH PIPE CAN BE INSTALLED IN ONE DAY'S TIME SHALL BE OPEN AT ANY TIME, WITH SPOIL MATERIAL PLACED ON THE UPHILL SIDE OF THE TRENCH. PIPING SHALL BE CAPPED AT END OF EACH WORK DAY TO PREVENT SEDIMENT FROM ENTERING. TRENCHES SHALL BE BACKFILLED AT END OF EACH WORK DAY AND DISTURBED AREA SEEDED WITH TEMPORARY SEEDING MEASURES AS NECESSARY.
- 8. EARTHWORK EXCAVATION AND FILL OPERATIONS, AS WELL AS PUMP STATION CONSTRUCTION, SHALL BE PERFORMED IN ACCORDANCE WITH STANDARD CONSTRUCTION TECHNIQUES. ALL EXCAVATION DEWATERING FLOWS SHALL PASS THROUGH A SEDIMENT FILTERING DEVICE PRIOR TO DISCHARGE. TOPSOIL SHALL BE STRIPPED AND STOCKPILED ON SITE. TOPSOIL STOCKPILE SHALL HAVE PERIMETER EROSION CONTROL MEASURES INSTALLED AND SEEDED WITH TEMPORARY SEEDING MEASURES DURING CONSTRUCTION ACTIVITIES.
- 9. STORM DRAINAGE DITCHES SHALL BE PROTECTED WITH APPROPRIATE EROSION CONTROL MEASURES AT ALL TIMES. POSITIVE STORMWATER DRAINAGE AWAY FROM CONSTRUCTION ACTIVITIES SHALL BE MAINTAINED AT ALL TIMES DURING CONSTRUCTION.
- 10. TEMPORARY SEEDING MEASURES SHALL BE EMPLOYED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT WHERE STABILIZATION MEASURES WOULD BE PRECLUDED BY SNOW OR FROZEN GROUND CONDITIONS, OR WHERE CONSTRUCTION ACTIVITY WILL BE RESUMED WITHIN 14 DAYS.
- 11. ONCE ALL EARTHWORK AND CONSTRUCTION ACTIVITIES ARE COMPLETE, FINAL GRADING MAY BEGIN. CONTRACTOR SHALL FILE A NOTICE OF TERMINATION TO SCDHEC.
- 12. UPON COMPLETION OF FINAL GRADING, PERMANENT SEEDING, MULCHING, AND FERTILIZING MEASURES

SHALL BE EMPLOYED ON ALL DISTURBED AREAS AS SPECIFIED IN THE CONTRACT DOCUMENTS. ALL EROSION CONTROL MEASURES SHALL REMAIN IN PLACE UNTIL ENTIRE SITE HAS BEEN STABILIZED.

13. ONCE PERMANENT STABILIZATION HAS OCCURRED AND APPROVED BY LOCAL AUTHORITIES, CONTACTOR SHALL FILE A NOTICE OF TERMINATION (NOT) AS PER THE REQUIREMENTS OF THIS SWPPP AND THE SOUTH CAROLINA NPDES GENERAL PERMIT FOR STORMWATER DISCHARGES FROM CONSTRUCTION ACTIVITIES SCR100000. ANY AREAS DISTURBED BY THE REMOVAL OF THESE MEASURES SHALL BE RETURNED AS CLOSELY AS POSSIBLE TO ORIGINAL CONDITION AND SEEDED, MULCHED, AND FERTILIZED AS SPECIFIED IN THE CONTRACT DOCUMENTS.

SEDIMENT AND EROSION CONTROL

- 1. IF NECESSARY, SLOPES WHICH EXCEED EIGHT (8)
 VERTICAL FEET SHOULD BE STABILIZED WITH
 SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO
 HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL
 TEMPORARY SLOPE DRAINS DURING CONSTRUCTION.
 TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE
 IS BROUGHT TO GRADE.
- 2. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW.
 - WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE.
 - WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.
- 3. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY CALENDAR WEEK. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY OR INCORRECTLY INSTALLED, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN 48 HOURS OF IDENTIFICATION.
- 4. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING PER SPECS IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE SEDIMENT BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.
- 5. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
- 6. THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.
- 7. RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE AS WELL AS FOR INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH S.C REG. 72-300 ET SEQ. AND SCR100000.
- 8. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.
- ALL WATERS OF THE STATE (WoS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE

CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WoS. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WoS.

- 10. LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.
- 11. A COPY OF THE SWPPP, INSPECTIONS RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.
- 12. INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:1V OR GREATER) WHERE LAND-DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS.
- 13. MINIMIZE SOIL COMPACTION AND, UNLESS INFEASIBLE, PRESERVE TOPSOIL.
- 14. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE.
- 15. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMPS (SEDIMENT BASIN, FILTER BAG, ETC.).
- 16. THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED:
 - WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL;
 - WASTEWATER FROM WASHOUT AND CLEAN OUT OF STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS;
 - FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE; AND
 - SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING.
- 17. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
- 18. IF EXISTING BMPS NEED TO BE MODIFIED OR IF ADDITIONAL BMPS ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND/OR SC'S WATER QUALITY STANDARDS, IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE. IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE, THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPS MUST BE IMPLEMENTED AS SOON AS REASONABLY POSSIBLE.
- 19. A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB 10 ACRES OR MORE THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT HAS APPROVED OTHERWISE.

SEEDING SCHEDULE

SCHEDULE NO.	COMMON SEED NAME	APPLICATION RATE (lb/acre)	PLANTING DATES
TEMPORARY			
1	Rye (grain) Rye (oats)	56 75	September 1 - March 15
2	Ryegrass	50	September 1 - April 15
3	Browntop or Japanese Millet	40	March 15 - August 31

NOTE

1. All seeded areas shall receive 500#/AC 10-10-10 fertilizer and 1500 - 2000#/AC straw mulch.

PERMANENT

1	Rye (grain) Bahiagrass Crimson Clover (annual)	10 40	September 1 - November 10
2	Browntop Millet	5 10	March 15 - August 31
	Bahiagrass	30	J
	Sericea Lespedeza	40	

NOTES

- 1. Other acceptable coastal grass blends can be found in Appendix C "Temporary and Permanent Seeding Rate Tables" of the SCDHEC Stormwater Management BMP Field Manual.
- All seeded areas shall receive 3000#/AC ground course textured agricultural limestone, 1000#/AC 10-10-10 fertilizer, and 4000#/AC straw mulch.
- 3. Application Method:

Application Method	Ground Slope
Broadcast Seeding (Unmulched)	0 - 2%
Broadcast Seeding (Mulched)	2 - 10%
Hydroseeding	Greater than 10%



PROJECT J. HARTWIG **ENGINEER: DESIGNED BY:** L FANNING DRAWN BY: L FANNING CHECKED BY: IF THIS BAR DOES NOT CONSTRUCTION JAN 2020 HAZEN MEASURE 1" THEN DRAWING IS NOT TO FULL SCALE **ISSUED FOR** DATE





MOUNT PLEASANT, SOUTH CAROLINA 29464



Charleston Water System


COMMISSIONERS OF PUBLIC WORKS
OF THE CITY OF CHARLESTON, SC


THOMAS ISLAND REGIONAL PUMP STATION
AND INTERCEPTOR
DIVISION I & II


GENERAL
CIVIL NOTES

DATE: JANUARY 2020
HAZEN NO.: 30533-008
CONTRACT NO.: 01
DRAWING NUMBER:

C001







MOUNT PLEASANT, SOUTH CAROLINA 29464

DIVISION I


C102


JAN 2020 HAZEN

DATE

CONSTRUCTION

ISSUED FOR





HAZEN AND SAWYER

735 JOHNNIE DODDS BLVD, SUITE 102 MOUNT PLEASANT, SOUTH CAROLINA 29464

AND INTERCEPTOR

DIVISION I

DRAWING NUMBER:

C104

STAKING AND PAVING PLAN

CONSTRUCTION

ISSUED FOR

C. RAGOS


CHECKED BY:


JAN 2020 HAZEN


DATE

IF THIS BAR DOES NOT
MEASURE 1" THEN DRAWING
IS NOT TO FULL SCALE

0 1/2" 1"








APPROXIMATE SOIL BORING LOCATION

OVERALL KEY PLAN 1" = 300'

9 _Z					PROJECT ENGINEER:	J. HARTWIG	
: LFANNING					DESIGNED BY:	L. FANNING	
S AM BY:					DRAWN BY:	L. FANNING	
4/23/2020 8:36					CHECKED BY:	C. RAGOS	
	1	CONSTRUCTION	JAN 2020	HAZEN	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING	0 1/2" 1"	
T DATE:	DE\/	ISSUED FOR	DATE	RV	IS NOT TO FULL SCALE		









THOMAS ISLAND REGIONAL PUMP STATION
AND INTERCEPTOR
DIVISION I & II

CLEMENTS FERRY RD GRAVITY SEWER CIVIL OVERALL KEY PLAN

DATE:	JAN	UARY	2020
HAZEN NO	.:	30533	3-008
CONTRACT	NO.:		01
DRAWING			

C200





PROFILE - CLEMENTS FERRY RD GRAVITY SEWER

H: 1" = 30' V: 1" = 6'

CHS\30533-008\DESIGN\DRAWINGS\CIVI 23/2020 8:37 AM BY: LFANNING					PROJECT ENGINEER:	J. HARTWIG	
SN\DRAWING ': LFANNING					DESIGNED BY:	L. FANNING	
008\DESIG					DRAWN BY:	L. FANNING	
s\30533-0(2020 8:37					CHECKED BY:	C. RAGOS	
	2	ADDENDUM No. 1	JAN 2020	HAZEN	IF THIS BAR DOES NOT	0 1/2" 1"	1
O:\30533 T DATE: 4	1	CONSTRUCTION	JAN 2020	HAZEN	MEASURE 1" THEN DRAWING	0 1/2" 1"	1
: 0:\3	RFV	ISSUED FOR	DΔTF	BY	IS NOT TO FULL SCALE		1






Charleston Water System
COMMISSIONERS OF PUBLIC WORKS OF THE CITY OF CHARLESTON, SC

THOMAS ISLAND REGIONAL PUMP STATION
AND INTERCEPTOR
DIVISION I & II

CLEMENTS FERRY RD
GRAVITY SEWER
CIVIL
STA 0+00 TO STA 7+80

DATE:	JANUARY 2020
HAZEN NO	.: 30533-008
CONTRACT	T NO.: 01
DRAWING NUMBER:	
	C201



SILT FENCE INSTALLATION 1.25 LB./LINEAR FT. STEEL POSTS FILTER FABRIC HEAVY DUTY PLASTIC TIE FOR STEEL POSTS (RESTRICT TO TOP 8-INCHES OF FABRIC) COMPACTED EARTH _ USE EITHER FLAT-BOTTOM OR V-BOTTOM TRENCH SEE DETAILS BURY FABRIC

INSPECTION AND MAINTENANCE:

2"x2" WOOD

STAKES OR 1.25#/ FT STEEL POST —

24' SPACING (TYP)

CONTINUOUS ALONG

INSPECTION AND MAINTENANCE:

CONSTRUCTION SITE CONDITIONS.

CONSTRUCTION

ISSUED FOR

TUBE —

- 1. INSPECT EVERY 7 CALENDAR DAYS AND WITHIN 24-HOURS AFTER EACH RAINFALL EVENT THAT PRODUCES 1/2 INCHES OR MORE OF PRECIPITATION. CHECK FOR SEDIMENT BUILDUP AND FENCE INTEGRITY. CHECK WHERE RUNOFF HAS ERODED A CHANNEL BENEATH THE FENCE, OR WHERE THE FENCE HAS SAGGED OR COLLAPSED BY FENCE OVERTOPPING.
- 2. IF THE FENCE FABRIC TEARS, BEGINS TO DECOMPOSE, OR IN ANY WAY BECOMES INEFFECTIVE, REPLACE THE SECTION OF FENCE IMMEDIATELY.
- 3. REMOVE SEDIMENT ACCUMULATED ALONG THE FENCE WHEN IT REACHES 1/3 THE HEIGHT OF THE FENCE, ESPECIALLY IF HEAVY RAINS ARE EXPECTED.
- 4. REMOVE TRAPPED SEDIMENT FROM THE SITE OR STABILIZE IT ON SITE.
- 5. REMOVE SILT FENCE WITHIN 30 DAYS AFTER FINAL STABILIZATION IS ACHIEVED OR AFTER TEMPORARY BEST MANAGEMENT PRACTICES ARE NOT LONGER NEEDED.
- PERMANENTLY STABILIZE DISTURBED AREAS RESULTING FROM FENCE REMOVAL

LESS THAN 2%

4%

GREATER THAN 6%

- 24" MIN

1. INSPECT SEDIMENT TUBES AFTER INSTALLATION FOR GAPS UNDER THE SEDIMENT TUBES AND FOR GAPS

4. REMOVE ALL SEDIMENT DEPOSITS THAT IMPAIR THE FILTRATION CAPABILITY OF SEDIMENT TUBES WHEN THE

6. REMOVE SEDIMENT TUBES FROM THE SITE WHEN THE FUNCTIONAL LONGEVITY IS EXCEEDED AS DETERMINED

BY THE ENGINEER, INSPECTOR, OR MANUFACTURER'S REPRESENTATIVE. GATHER SEDIMENT TUBES AND

IF THIS BAR DOES NOT

IS NOT TO FULL SCALE

MEASURE 1" THEN DRAWING

2. INSPECT EVERY 7 DAYS AND WITH 24-HOURS OF A RAINFALL EVENT OF 1/2 INCHES OR GREATER.

5. REMOVE AND/OR REPLACE INSTALLED SEDIMENT TUBES AS REQUIRED TO ADAPT TO CHANGING

7. PRIOR TO FINAL STABILIZATION, BACKFILL ALL TRENCHES, DEPRESSIONS, AND OTHER GROUND

DISPOSE OF THEM IN A REGULAR MEANS AS NON-HAZARDOUS, INERT MATERIAL.

END VIEW OF DITCH

BETWEEN THE JOINTS OF ADJACENT ENDS OF SEDIMENT TUBES.

DISTURBANCES CAUSED BY THE REMOVAL OF SEDIMENT TUBES.

3. REPAIR ALL RILLS, GULLIES, AND UNDERCUTTING NEAR SEDIMENT TUBES.

SEDIMENT REACHES 1/3 THE HEIGHT OF THE EXPOSED SEDIMENT TUBE.

SEDIMENT TUBE SPACING

MAXIMUM SEDIMENT TUBE SPACING

150-FEE


100-FEE

75-FEET


50-FEET

40-FEET

1. DO NOT PLACE SILT FENCE ACROSS CHANNELS OR IN OTHER AREAS SUBJECT TO FLAT-BOTTOM TRENCH DETAIL



V-SHAPED TRENCH DETAIL



- CONCENTRATED FLOWS. SILT FENCE SHOULD NOT BE USED AS A VELOCITY CONTROL BMP. CONCENTRATED FLOWS ARE GREATER THAN 0.5cfs. 2. MAXIMUM SHEET OR OVERLAND FLOW PATH LENGTH TO THE SILT FENCE SHALL BE 100
- 3. MAXIMUM SLOPE STEEPNESS (NORMAL [PERPENDICULAR] TO THE FENCE LINE) SHALL BE
- 2:1. 4. SILT FENCE JOINTS, WHEN NECESSARY, SHALL BE COMPLETED BY ONE OF THE
 - WRAP EACH FABRIC TOGETHER AT A SUPPORT POST WITH BOTH ENDS FASTENED TO THE POST, WITH A 1 FOOT MINIMUM OVERLAP;
 - OVERLAP SILT FENCE BY INSTALLING 3 FEET PASSED THE SUPPORT POST TO WHICH THE NEW SILT FENCE ROLL IS ATTACHED. ATTACH OLD ROLL T NEW ROLL WITH HEAVY-DUTY PLASTIC TIES; OR,
 - OVERLAP ENTIRE WIDTH OF EACH SILT FENCE ROLL FROM ONE SUPPORT POST TO THE NEXT SUPPORT POST.
- 5. ATTACH FILTER FABRIC TO THE STEEL POSTS USING HEAVY-DUTY PLASTIC TIES THAT ARE EVENLY SPACED WITHIN THE TOP 8 INCHES OF THE FABRIC.
- INSTALL THE SILT FENCE PERPENDICULAR TO THE DIRECTION OF THE STORMWATER FLOW AND PLACE THE SILT FENCE THE PROPER DISTANCE FROM THE TOE OF STEEP SLOPES TO PROVIDE SEDIMENT STORAGE AND ACCESS FOR MAINTENANCE AND
- 7. INSTALL SILT FENCE CHECKS (TIE-BACKS) EVERY 50-100 FEET, DEPENDENT ON SLOPE, ALONG SILT FENCE THAT IS INSTALLED WITH SLOPE AND WHERE CONCENTRATED FLOWS ARE EXPECTED OR ARE DOCUMENTED ALONG THE PROPOSED/INSTALLED SILT FENCE.

SILT FENCE

FOLLOWING OPTIONS:

0227000R


STAKES PLACED

AT 24" MIN

SPACING


SEDIMENT TUBE NOTES:


- 1. SEDIMENT TUBES ARE ELONGATED TUBES OF COMPACTED GEOTEXTILES, CURLED EXCELSION WOOD, NATURAL COCONUT FIBER OR HARDWOOD MULCH. STRAW, PINE AND LEAF MULCH-FILLED SEDIMENT TUBES ARE NOT PERMITTED.
- 2. INSTALL SEDIMENT TUBES ALONG CONTOURS, IN DRAINAGE CONVEYANCE SWALES, AND AROUND INLETS TO HELP REDUCE THE EFFECTS OF SOIL EROSION BY ENERGY DISSIPATION AND RETAIN SEDIMENT.
- SEDIMENT TUBES FOR DITCH CHECKS AND TYPE A INLET STRUCTURE FILTERS EXHIBIT THE FOLLOWING PROPERTIES:
 - PRODUCED BY A MANUFACTURER EXPERIENCED IN SEDIMENT TUBE MANUFACTURING. • COMPOSED OF COMPACTED GEOTEXTILES, CURLED EXCELSIOR WOOD, NATURAL COCONUT FIBERS, HARDWOOD MULCH OR A MIX OF THESE MATERIALS ENCLOSED BY A FLEXIBLE NETTING MATERIAL.
 - STRAW, PINE AND LEAF MULCH-FILLED SEDIMENT TUBES ARE NOT PERMITTED. UTILIZES OUTER NETTING THAT CONSISTS OF SEAMLESS, HIGH-DENSITY POLYETHYLENE PHOTODEGRADABLE MATERIALS TREATED WITH ULTRAVIOLET STABILIZERS OR A SEAMLESS, HIGH-DENSITY POLYETHYLENE NON-DEGRADABLE MATERIALS. DIAMETER RANGING FROM 18-INCH TO 24-INCHES.
 - CURLED EXCELSIOR WOOD, OR NATURAL COCONUT ROLLED EROSION CONTROL PRODUCTS (RECPS) THAT ARE ROLLED UP TO CREATE A SEDIMENT TUBE ARE NOT ALLOWED.
- 4. INSTALL OVER BARE SOIL, MULCH AREAS OR EROSION CONTROL BLANKETS. TO BE COMPOSED OF GEOTEXTILES, CURLED EXCELSIOR WOOD, NATURAL COCONUT FIBER OR HARDWOOD MULCH ENCLOSED BY A FLEXIBLE NETTING MATERIAL.
- 5. THE MINIMUM DIAMETER SHOULD BE 18-INCHES. SEDIMENT TUBES SHOULD BE STAKED USING WOODEN STAKES (2-INCHX2-INCH) OR STEEL POSTS (STANDARD "U" OR "T" SECTIONS WITH A MINIMUM WEIGHT OF 1.25 POUNDS PER FOOT) A MINIMUM OF 48-INCHES IN LENGTH PLACED ON 2-FOOT CENTERS.
- STAKES SHOULD BE INTERTWINED WITH THE OUTER MESH ON THE DOWN STREAM SIDE AND DRIVEN IN THE GROUND TO A MINIMUM DEPTH OF 1.5 FEET LEAVING LESS THAN 1 FOOT OF STAKE EXPOSED ABOVE THE SEDIMENT TUBE. ALWAYS REFER TO THE MANUFACTURER'S RECOMMENDATIONS FOR THE STAKING DETAIL. INSTALL ALL SEDIMENT TUBES INSURING THAT NO GAPS EXIST BETWEEN THE SOIL AND THE BOTTOM OF THE SEDIMENT TUBE. THE ENDS OF ADJACENT SEDIMENT TUBES SHOULD BE LAPPED 6-INCH TO PREVENT FLOW AND SEDIMENT FROM PASSING THROUGH THE FIELD JOINT. IN NO SITUATION SHOULD SEDIMENT TUBES BE STACKED ON TOP OF ONE ANOTHER.
- 7. CONSTRUCT A TRENCH THAT IS 20% OF THE TUBE DIAMETER TO INSTALL THE TUBE IN. AVOID DAMAGE TO SEDIMENT TUBES WHILE INSTALLING THEM. IF THE SEDIMENT TUBES BECOMES DAMAGED DURING INSTALLATION, A STAKE SHOULD BE PLACED ON BOTH SIDES OF THE DAMAGED AREA TERMINATING THE TUBE SEGMENT AND A NEW TUBE SEGMENT SHOULD BE INSTALLED IN SWALES OR DRAINAGE DITCHES PERPENDICULAR TO THE DEPTH. SEDIMENT TUBES SHOULD CONTINUE UP THE SIDE SLOPES A MINIMUM OF 1 FOOT ABOVE THE DESIGN FLOW DEPTH. SEDIMENT TUBES SHOULD BE SPACED ACCORDING TO THE SEDIMENT TUBE SPACING TABLE.
- SEDIMENT TUBE LENGTH SELECTED SHOULD MINIMIZE THE NUMBER OF SEDIMENT TUBES NEEDED TO SPAN THE WIDTH OF THE DRAINAGE CONVEYANCE. IF THE DITCH CHECK LENGTH (PERPENDICULAR TO THE FLOW) IS 15 FEET, THEN ONE 15 FOOT SEDIMENT TUBE IS PREFERRED COMPARED TO TWO OVERLAPPING 10 FOOT SEDIMENT TUBES.






MINIMUM BEDDING FOR GRAVITY SEWER LINE CWS DETAIL 41







ANTI-SEEPAGE COLLAR 0260113

PLAN

TRENCH WIDTH

VARIES

SECTION

PIPELINE


(DIAMETER VARIES)

- CLASS B CONCRETE

CLASS B CONCRETE

CURB INLET SEDIMENT CONTROL

0227002



PIPE ZONE CLASS II BACKFILL IN 6" LIFTS AND COMPACTED BC CLASS II BACKFILL IN BC	TAPF
UNDISTURBED SOIL TRACER WIRE TAPED TO PIPE SEE NOTE 4. UNDISTURBED SOIL ENTIRE BARREL OF PIPE TO REST ON BOTTOM OF TRENCH	 REFER TO SCDOT HIGHWAY DEPARTMENT, CITY OR COUNTY PERMITS FOR ADDITIONAL REQUIREMENTS. IF UNSUITABLE MATERIAL BENEATH FINAL PIPE GRADE IS ENCOUNTERED, SUCH MATERIAL SHALL BE REMOVED AND REPLACED WITH CRUSHED STONE AND COMPACTED TO PROPER GRADE. ANY DEBRIS ENCOUNTERED IN THE TRENCH EXCAVATION SHALL BE REMOVED. REFER TO THE TRACER WIRE AND MAGNETIC TAPE DETAIL #66 FOR ADDITIONAL INFORMATION.
FORCEMAIN BEDDING CWS DETAIL 51	

PROJECT J. HARTWIG **ENGINEER: DESIGNED BY:** L. FANNING DRAWN BY: L. FANNING C. RAGOS CHECKED BY:

JAN 2020 HAZEN

DATE



SEDIMENT TUBE DETAILS

NOT TO SCALE

TOP VIEW OF DITCH

Hazen HAZEN AND SAWYER

735 JOHNNIE DODDS BLVD, SUITE 102

MOUNT PLEASANT, SOUTH CAROLINA 29464





THOMAS ISLAND REGIONAL PUMP STATION AND INTERCEPTOR DIVISION I & II

CIVIL STANDARD DETAILS

DATE:	JAN	UARY 2020
HAZEN NC).:	30533-008
CONTRACT	Γ NO.:	01
DRAWING NUMBER:		

C900






NOTES:

- 1. SILT FENCE TO EXTEND AROUND ENTIRE PERIMETER OF STOCKPILE, OR IF STOCKPILE AREA IS LOCATED ON/NEAR A SLOP THE SILT FENCE IS TO EXTEND ALONG CONTOURS OF THE DOWN-GRADIENT AREA.
- 2. IF STOCKPILE IS TO REMAIN FOR MORE THAN 14 DAYS, TEMPORARY STABILIZATION MEASURES MUST BE IMPLEMENTED.
- 3. SILT FENCE SHALL BE MAINTAINED UNTIL STOCKPILE AREA HAS EITHER BEEN REMOVED OR PERMANENTLY STABILIZED.
- 4. THE KEY TO FUNCTIONAL TEMPORARY STOCKPILE AREAS IS WEEKLY INSPECTIONS, ROUTINE MAINTENANCE, AND REGULAR SEDIMENT REMOVAL.

TEMPORARY STOCKPILE AREA





NOTES:

- 1. ACTUAL LAYOUT DETERMINED IN FIELD.
- 2. INSTALL CONCRETE WASHOUT SIGN (24"X24", MINIMUM) WITHIN 30' OF THE TEMPORARY CONCRETE WASHOUT FACILITY.
- 3. TEMPORARY WASHOUT AREA MUST BE AT LEAST 50' FROM A STORM DRAIN, CREEK BANK OR PERIMETER CONTROL.
- 4. CLEAN OUT CONCRETE WASHOUT AREA WHEN 50% FULL.

WITH STRAW BALES

- 5. THE KEY TO FUNCTIONAL CONCRETE WASHOUTS IS WEEKLY INSPECTIONS, ROUTINE MAINTENANCE, AND REGULAR CLEAN OUT.
- 6. SILT FENCE SHALL BE INSTALLED AROUND PERIMETER OF CONCRETE WASHOUT AREA EXCEPT FOR THE SIDE UTILIZED FOR ACCESSING THE WASHOUT.
- 7. A ROCK CONSTRUCTION ENTRANCE MAY BE NECESSARY ALONG ONE SIDE OF THE WASHOUT TO PROVIDE VEHICLE ACCESS.


STRAW BALE BARRIER CONCRETE WASHOUT




- 12 IN WIDE BAND

14 GA T-304 S.S.


- 10GA T-304 S.S. RISERS





BACKFLOW PREVENTION ASSEMBLY

DETAIL	5
CWS DETAIL 33	C103




TYPICAL CASING FOR

0232201R

JACK AND BORE

CARRIER PIPE-5/16" SST BOLT CASING PIPE 3/16 4 UHMW POLYMER RUNNERS CASING SPACER 0232200R



PROJECT J. HARTWIG **ENGINEER:** L. FANNING **DESIGNED BY:** DRAWN BY: L. FANNING C. RAGOS CHECKED BY: IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING 0 1/2" 1" CONSTRUCTION JAN 2020 HAZEN

DATE

ISSUED FOR

IS NOT TO FULL SCALE

HAZEN& SAWYER C00638

Hazen HAZEN AND SAWYER 735 JOHNNIE DODDS BLVD, SUITE 102 MOUNT PLEASANT, SOUTH CAROLINA 29464




THOMAS ISLAND REGIONAL PUMP STATION AND INTERCEPTOR DIVISION I & II

CIVIL STANDARD DETAILS

0257701R

DATE: JAN	NUARY 2020
HAZEN NO.:	30533-008
CONTRACT NO.:	01
DRAWING NUMBER:	
	C902



735 JOHNNIE DODDS BLVD, SUITE 102

MOUNT PLEASANT, SOUTH CAROLINA 29464

AND INTERCEPTOR

DIVISION I & II

NUMBER:

C903

File: 0:\30533-CHS\30533-008\DES


CONSTRUCTION

ISSUED FOR

JAN 2020 HAZEN

DATE

IF THIS BAR DOES NOT
MEASURE 1" THEN DRAWING
IS NOT TO FULL SCALE



MOUNT PLEASANT, SOUTH CAROLINA 29464

DIVISION I & II

C904

CONSTRUCTION


ISSUED FOR

JAN 2020 HAZEN

DATE

IS NOT TO FULL SCALE

0 1/2" 1"



SEWER CROSSING ABOVE WATER MAIN

NOTES FOR SEWER OVER WATER MAIN:


PROPOSED SEWER

INSTALL A FULL JOINT OF PIPE FOR WHICHEVER MAIN IS LAID SECOND. IT IS TO BE CENTERED AT CROSSING.
 IF THE WATER IS EXISTING AND THE MINIMUM CLEARANCE IS NOT MET, THE SEWER SHALL BE PVC C900, C905, OR DUCTILE IRON PIPE. PROVIDE RESTRAINED JOINT FITTINGS WHEN TRANSITIONING FROM DIP TO PVC. PLACE FLOWABLE FILL BETWEEN TOP OF WATER MAIN AND BOTTOM OF SEWER.
 IF THE SEWER IS EXISTING, THE WATER MAIN SHALL MEET THE MINIMUM CLEARANCE.

EXISTING WATER MAIN

NOTES FOR SEWER UNDER WATER MAIN:

- SOIL REPLACED UNDER THE WATER MAIN SHALL BE COMPACTED AS PER CWS MINIMUM STANDARDS FOR WATER MAIN INSTALLATION. 2. IF CLEARANCE IS LESS THAN 18", PVC C900, C905 OR DUCTILE IRON PIPE
- SHALL BE USED. PROVIDE RESTRAINED JOINT FITTINGS WHEN TRANSITIONING FROM DIP TO PVC. PLACE FLOWABLE FILL BETWEEN TOP OF SEWER AND BOTTOM OF WATER MAIN. PLACE A LAYER OF POLYWRAP ABOVE SEWER 3. INSTALL A FULL JOINT OF PIPE FOR WHICHEVER MAIN IS LAID SECOND. IT IS TO BE CENTERED AT CROSSING.




SEWER CROSSING UNDER WATER MAIN

SEWER MAIN CROSSING WATER MAIN NOT TO SCALE

TYPICAL SEWER MAIN ROAD CUT

CWS DETAIL 4:



1 ½" AND 2" WATER SERVICE NOT TO SCALE

2" WATER SERVICE

DETAIL 10 CWS DETAIL 21 --

				PROJECT ENGINEER:	J. HARTWIG
				DESIGNED BY:	L. FANNING
				DRAWN BY:	L. FANNING
				CHECKED BY:	C. RAGOS
1	CONSTRUCTION	JAN 2020	HAZEN	IF THIS BAR DOES NOT MEASURE 1" THEN DRAWING	0 1/2" 1"
REV	ISSUED FOR	DATE	BY	IS NOT TO FULL SCALE	









THOMAS ISLAND REGIONAL PUMP STATION AND INTERCEPTOR DIVISION I & II


DATE:	JAN	IUARY	2020
HAZEN NO	.:	30533	3-008
CONTRACT	NO.:		01
DRAWING NUMBER:			

C905

CIVIL STANDARD DETAILS







735 JOHNNIE DODDS BLVD, SUITE 102

MOUNT PLEASANT, SOUTH CAROLINA 29464

AND INTERCEPTOR

DIVISION I

AND PANEL SCHEDULE

NUMBER:

E102

JAN 2020 HAZEN JAN 2020 HAZEN

IF THIS BAR DOES NOT

IS NOT TO FULL SCALE

MEASURE 1" THEN DRAWING

ADDENDUM No. 1

CONSTRUCTION

ISSUED FOR

FROM